



ENGINEERING MEMORANDUM

To: Town of Monroe, Application Review Team

From: Kevin Solli, P.E. / Solli Engineering
Chris Pawlowski, EIT / Solli Engineering

Subject: Excavation / Filling Permit Application
10 & 36 Main Street, Monroe, Connecticut 06468

Date: July 26, 2021

CC: Arnold Karp / Karp Associates, Inc.

Solli Engineering, LLC has prepared this Memorandum to provide an analysis of the earthwork, zoning compliance, grading design, soil erosion control measures and stormwater management associated with the proposed excavation/filling activity located at 10 & 36 Main Street in Monroe, Connecticut. The design is in compliance with applicable Town of Monroe regulations as well as other applicable state and federal requirements. The following summarizes the proposed project activities.

Property Description:

The project site is comprised of 10 & 36 Main Street in Monroe, Connecticut. The total site is approximately 14.35 acres, comprised of 5.22 acres within 10 Main Street and 9.13 acres within 36 Main Street. The site is bound by Main Street (Route 25) to the west, Victoria Drive to the north, and commercial developed land to the east and south. Both properties are owned by 10 & 36 Main Street LLC and zoned Business District 2 (B-2). See Figure 1, Site Location Map, for a depiction of the project location.

The project site was visited by a certified soil scientist from William Kenny Associates, LLC on April 22, 2021. William Kenny Associates determined that one inland wetland system was identified and delineated. The system, which is located in the eastern portion of 10 Main Street, is a woodland wetland. No wetland soils or watercourses were found within the property of 36 Main Street. See the Wetland Delineation Report, prepared by William Kenny Associates, LLC for additional detail on the site wetlands assessment.

Property History:

Prior to 1984, 36 Main Street consisted of land totaling approximately 2.35 acres and was bounded by Main Street (Route 25) to the west, a children's camp to the north, a former railway to the east and 10 Main Street to the south. A residential dwelling occupied this property at that time but was later demolished. In 1984, a land transfer of the railway parcel and a portion of the children's camp site were deeded over to 36 Main Street creating the current 5.4-acre parcel. This land was occupied by a dwelling unit and driveway associated with the camp site; these site features

**501 Main Street, Suite 2A
Monroe, CT 06468
Office: (203) 880-5455**

**351 Newbury Street, Suite 303
Boston, MA 02115
Office: (617) 203-3160**

have since been demolished. The site has remained vacant since these features were demolished. Over the years, the site has grown over with woody vegetation, consisting of evergreens and deciduous trees.

The property at 10 Main Street was previously occupied by a $\pm 34,000$ SF building and an additional $\pm 11,567$ warehouse. The buildings were owned and operated by Vishay Intertechnology, Inc. the buildings were demolished at some time in 2013, and the site has remained vacant since that time.

Project Narrative:

The project proposes to import approximately 167,790 cubic yards of fill material from various sites to 10 & 36 Main Street, to fill to an average elevation of approximately 328 feet. The project proposes to place fill over an area on the property, which is subject to an environmental land use restriction, while the balance of the fill is proposed to support future site development. A substantial portion of the fill will be sourced from the property of 127 Main Street as part of the site development project approved by the Town of Monroe Inland Wetlands and Planning & Zoning Commissions. The project site can be accessed off Main Street (Route 25), which will serve as the main site entrance. Temporary construction fence is to be placed along Main Street. See the Cut/Fill Analysis Plan, Figure 7, for additional details.

The soil erosion and sediment control measures proposed for the filling activity have been designed in accordance with the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control. The soil erosion and sediment control measures proposed as part of this project include mulch berms, geotextile silt fences, stone check dams, temporary diversion swales, construction entrances, dust control measures, riprap stabilization, silt sack inlet protection for existing drainage features, and a sediment basin. During construction, this basin will detain sediment-laden runoff from contributing drainage areas. The sediment basin is proposed in a low-lying area and has been sized to provide a minimum storage as required per the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control. Sediment Basin #1 is located at the northeastern end of the property. See plan Sheet 2.21, Grading & Soil Erosion Control Plan for more detail on the soil erosion and sediment control measures.

At the completion of the filling operation, the entire limit of disturbance will be seeded to provide stabilization and erosion control as well as provide improved curve numbers and time of concentrations compared to that of existing conditions, decreasing peak flows. At the completion of the project, the sediment will be removed from the basin and the sediment basin will be seeded and maintained to provide additional storm water detention until future potential development commences. A progress reporting form has also been prepared for the project and can be found in Appendix C.

Drainage Analysis:

The stormwater management plan and design for 10 & 36 Main Street is intended to be in compliance with the 2004 Connecticut Stormwater Quality Manual, while taking prevailing site conditions and practical considerations into account.

Stormwater runoff analysis, for both existing and proposed conditions, was performed using the software package Hydroflow Hydrograph Extension. This software uses computer implementation of the SCS-TR-55 methodology to compute volumes and rates of runoff. The watershed area, rainfall depths and intensity, curve number and time of concentration are factors that influence the computed results and are shown in the Hydrology Report in Appendix B.

Rainfall depths were taken from NOAA’s National Weather Service Atlas 14, Point Precipitation Frequency Estimates and were used for calculating the volumes and rates of runoff for this project. The depths are listed in Table 1 below:

Table 1: Rainfall Data

Return Period	24-hr Rainfall Depth (in)
2-year	3.56
5-year	4.63
10-year	5.51
25-year	6.72
50-year	7.62
100-year	8.60

Hydraflow Hydrographs Extension automatically computes the rainfall intensity from its own IDF curves when the rainfall intensity data is provided. Table 2 shows the data that was used to generate the IDF curves. This information was taken from the NOAA’s National Weather Service Atlas 14, Point Precipitation Frequency Estimates.

Table 2: IDF Table

Intermediate Intensity Values (in/hr)				
Return Period	5-Minute	15-Minute	30-Minute	60-Minute
2-year	5.10	2.83	1.97	1.26
5-year	6.31	3.51	2.44	1.56
10-year	7.32	4.07	2.83	1.81
25-year	8.71	4.84	3.36	2.15
50-year	9.76	5.42	3.77	2.42
100-year	10.80	6.03	4.19	2.68

Existing Hydrology:

According to NRCS Soil Survey Geographic database for the State of Connecticut, the majority of the site is comprised of Canton and Charlton soils with 15 to 25 percent slopes. These soils have a hydrologic soil group rating of B. See Figure 3, Soil Survey Map, in Appendix A for more detail regarding soil boundaries.

Approximately 14.85 acres were analyzed for stormwater management purposes. Based on existing drainage patterns, the 14.85-acre area was considered one existing drainage area, labeled Existing Drainage Area 1 (EDA-1). The approximate location and delineation of this drainage area can be seen on Sheet DA-1, Existing Drainage Area Map, found in Appendix B.

EDA-1 has a contributing area of approximately 14.85 acres. This area encompasses the majority of the site starting at the crown within Main Street (Route 25) and reaching all the way east until the edge of the existing wetlands. The majority of runoff from EDA-1 flows east, overland, into the existing wetlands onsite. Pre-existing conditions were considered in the analysis, as 36 Main Street was previously comprised of mostly woods.

Characteristics of this drainage area is summarized in Table 3.

Table 3: Existing Drainage Area Characteristics

Drainage Area	Area (Acres)	Curve Number (CN)	Time of Concentration (Minutes)
EDA-1	14.71	72	17.5

Existing peak flows and volumes of runoff for all analyzed storm-events are summarized in Table 3. Calculations for the existing hydrology can be found in Appendix B.

Table 4: Existing Peak Flows

Drainage Area	Peak Flow (cfs)					
	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
EDA-1	13.79	23.65	32.43	45.06	54.79	65.55

Proposed Hydrology:

The proposed grading of the excavation/fill activity consists of drainage areas that are of similar patterns to existing contributing areas, within the 14.85 acres analyzed. Based on the proposed drainage patterns, the 14.85-acre area was divided into three (3) contributing drainage areas, labeled Proposed Drainage Area 1A (PDA-1A), Proposed Drainage Area 1B (PDA-1B) and Proposed Drainage Area 1C (PDA-1C). The approximate location and delineation of these drainage areas can be seen on Sheet DA-2, Proposed Drainage Area Map, found in Appendix B.

PDA-1A has a contributing area of approximately 12.03 acres. This encompasses the majority of the site covering from Route 25 all the way to the proposed Stormwater Basin #1. The majority of runoff from PDA-1A flows east, overland, into Stormwater Basin #1 located to the west of the existing wetlands area. PDA-1A is proposed to be seeded and established in the finished condition.

PDA-1B has a contributing area of approximately 1.81 acres. This area is comprised of southern end of the property, including grass and stone lined swales. Outside of the swales and existing woodlands, the area is to be seeded and established in the finished condition. Runoff from PDA-1B will travel east, overland, before entering the proposed swales and discharging into the existing wetlands along the eastern property line.

PDA-1C has a contributing area of approximately 1.01 acres. This area is comprised of the land directly to the west of the existing wetlands, most of which is existing woods that is to remain untouched. Runoff from PDA-1C will travel overland before reaching the existing wetlands onsite.

Characteristics of these drainage areas are summarized in Table 5. A map depicting proposed drainage areas can be found in Appendix B.

Table 5: Proposed Drainage Area Characteristics

Drainage Area	Area (Acres)	Curve Number (CN)	Time of Concentration (Minutes)
PDA-1A	12.03	61	26.6
PDA-1B	1.81	58	10.5
PDA-1C	1.01	47	10.8

Proposed peak flows and volumes for all analyzed storms are summarized in Table 5. Calculations for the proposed hydrology can be found in Appendix C.

Table 5: Proposed Peak Flows

Drainage Area	Peak Flow (cfs)					
	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
PDA-1A	4.05	9.02	13.89	21.37	27.36	34.18
PDA-1B	0.55	1.48	2.42	3.89	5.06	6.43
PDA-1C	0.02	0.19	0.46	1.02	1.52	2.12
Overall (PDA-1)	2.50	7.80	10.89	19.02	26.67	31.85

In an effort to improve the quality of the stormwater discharged from the site, the project will retain the water quality volume within the proposed Stormwater Quality Basin (Basin #1). Basin #1 will also provide additional storage for future development plans while as reducing the peak rate of runoff during the proposed excavation and filling activities. The basin is designed to provide a total storage capacity of approximately 26,615 cubic feet at a peak elevation of 298.82 during the 100-year storm to maximize the amount of detention on the site, with a required water quality volume of 3,708 cubic feet, and a provided stormwater quality volume of 3,885 cubic feet. With a top elevation of 300.00 for the proposed basin and a peak elevation of 298.82 during the 100-year storm, the basin provides a minimum of 1’ of freeboard. Stormwater is discharged from the water quality basin via an outlet control structure (OCS-1). The outlet control structure is a Connecticut State Highway Department, “C-L” top, standard catch basin configuration in which the top of frame acts as a weir. The outlet control structure features an 18” orifice with an invert of 294.50 and discharges through a 24” HDPE pipe to a level spreader. For more details on the configuration and drainage features of Stormwater Basin #1 and OCS-1, see Sheet 2.21, Grading & Soil Erosion Control Plan.

The proposed stormwater quality basin (Basin #1) is designed to attenuate the overall peak discharge rate for the 2-, 5-, 10-, 25-, 50-, and 100-year storm event; so that the overall proposed peak flow is less than the overall existing peak flow. The SCS TR-55 methodology was used to compute the peak discharge rates. Refer to Appendix B for calculations of the existing and proposed hydrology. The existing discharge rates and the proposed peak discharge rates, associated with the filling activities, are summarized in the table below (proposed rates are depicted in bold).

Table 6: Peak Flows Comparison

Drainage Area	Peak Flow (cfs)					
	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
EDA-1	13.79	23.65	32.43	45.06	54.79	65.55
PDA-1	2.50	7.80	10.89	19.02	26.67	31.85

In addition to the water quality volume provided in the stormwater quality basin, there are also two grass-lined swales proposed as a water quality measure. Both swales are proposed up-gradient of Basin #1. The swales both feature a 2’ depth with a longitudinal slope of 2%.

Post-Construction Site Maintenance:

The property owner shall maintain its property at 10 & 36 Main Street, Monroe, Connecticut in accordance with this site maintenance plan, as follows, to maintain the aesthetic quality and cleanliness of the site:

- There are to be no construction activities within the wetland areas, those areas will remain undisturbed as required.
- Main Street shall be checked for potential perimeter erosion, trash, spillage, and pavement conditions during these inspections.
- The sediment traps shall be inspected bi-annually in May and November and cleaned of excessive sediment and debris.
- Maintain each construction entrance anti-tracking pads with silt fence along the edge of the pads.

Earthwork Analysis:

The proposed excavation and filling project will have slopes that range from approximately 1.0 percent within the parking area to 30-50 percent within landscaped fill slopes around the edge of the project site. Elevations will range from a high of approximately 346 feet, in the northwest corner of the site, to a low of approximate 292 feet edge of the existing wetlands along the eastern property edge. The project was designed in order to raise the grades of the site to be closer to the elevations along Main Street (Route 25) in order to support future site development. There will be a proposed filling of 183,009 CY, and a cut of 15,219 CY, resulting in a net import of 167,790 CY. The majority of the excavation/ filling activities are to take place outside of the regulated area. Within the regulated area, there will be a proposed filling of 2,029 CY, and a cut of 2,680 CY, resulting in a net export of 651 CY. No fill is to be placed within the 100-year floodplain.

Supporting Documents:

Appendix A:

Figures

Site Location Map (Figure 1)
FEMA Flood Map (Figure 2)
Soil Survey Map (Figure 3)
National Diversity Database Map (Figure 4)
Regulated Area Map (Figure 5)
Slope Area Map (Figure 6)
Cut/Fill Exhibit (Figure 7)

Appendix B:

Hydrology

Existing Drainage Area Map (DA-1)
Proposed Drainage Area Map (DA-2)
NOAA Atlas Precipitation Data
Watershed Model Schematic
Hydraflow Stormwater Analysis
Hydraflow Return Period Recap Report
Hydraflow Summary Reports
Hydraflow Stormwater Pond Report
Curve Number Calculations
Time of Concentration Calculations
Water Quality Volume Calculations

Appendix C:

Inspections

Excavation/Fill Permit Progress Report Form


Appendix D:

Plans


Grading & Soil Erosion Control Plan (Sheet 2.21)
Reclamation Plan (Sheet 2.61)

APPENDIX A
FIGURES

- Site Location Map (Figure 1)
- FEMA Flood Map (Figure 2)
- Soil Survey Map (Figure 3)
- Natural Diversity Database Map (Figure 4)
- Regulated Area Map (Figure 5)
- Slope Area Map (Figure 6)
- Cut/Fill Exhibit (Figure 7)




NOTE: BASE MAP INFORMATION TAKEN FROM
[HTTP://CT.GOV/DOT](http://ct.gov/dot), MAP NUMBERS 084 AND 144



SOLLI
 ENGINEERING
 501 Main Street, Monroe, CT 06468
 T: (203) 880-5455 F: (203) 880-9695

SITE LOCATION MAP
 10 & 36 MAIN STREET
 MONROE, CONNECTICUT

Project #:	2008001
Plan Date:	07/26/21
Scale:	1" = 1000'
Figure:	1



Map unit symbol	Map unit name	Rating
38C	Hinckley loamy sand, 3 to 15 percent slopes	A
60B	Canton and Charlton fine sandy loams, 3 to 8 percent slopes	B
60D	Canton and Charlton soils, 15 to 25 percent slopes	B
108	Saco silt loam	B/D
306	Udorthents-Urban land complex	B

NOTE: BASE MAP INFORMATION TAKEN FROM THE
 NATURAL RESOURCES CONSERVATION SERVICE, URL:
[HTTP://WEBSOILSURVEY.NRCS.USDA.GOV](http://websoilsurvey.nrcs.usda.gov)
 DATE OF IMAGE: JUNE 03, 2021.



SOLLI
 ENGINEERING
 501 Main Street, Monroe, CT 06468
 T: (203) 880-5455 F: (203) 880-9695


SOIL SURVEY MAP
 10 & 36 MAIN STREET
 MONROE, CONNECTICUT

Project #: 2008001


Plan Date: 07/26/21

Scale: 1" = 300'

Figure: 3



NOTE: BASE MAP INFORMATION TAKEN FROM CT DEEP NATURAL DIVERSITY DATA BASE AREAS, MONROE, CT DECEMBER 2019 (MAP ND085.PDF)
 URL: [HTTPS://PORTAL.CT.GOV/DEEP/ENDANGERED-SPECIES/NATURAL-DIVERSITY-DATA-BASE-MAP](https://portal.ct.gov/deep/endangered-species/natural-diversity-data-base-map)




SOLLI
 ENGINEERING
 501 Main Street, Monroe, CT 06468
 T: (203) 880-5455 F: (203) 880-9695

NATURAL DIVERSITY MAP
 10 & 36 MAIN STREET
 MONROE, CONNECTICUT

Project #:	2008001
Plan Date:	07/26/21
Scale:	1" = 1000'
Figure:	4





GENERAL NOTES


1. WETLANDS WERE DELINEATED AND FLAGGED BY WILLIAM KENNY ASSOCIATES, LLC ON APRIL 22, 2021.



WETLAND AREA TABLE	
AREA	ACRES
PROPERTY AREA	14.35±
WETLANDS ON PROPERTY	0.86±
UPLAND REVIEW AREA ON PROPERTY	2.47±
WETLANDS TO BE ALTERED	0.00±
UPLAND REVIEW AREA TO BE ALTERED	1.19±
TOTAL REGULATED AREA TO BE ALTERED	1.19±

LEGEND

-  PROPERTY LINE
-  RIGHT-OF-WAY LINE
-  LIMIT OF WETLANDS
-  LIMIT OF UPLAND REVIEW AREA



Rev. #:	Date	Description

SOLLI ENGINEERING
 501 Main Street, Monroe, CT 06468
 T: (203) 880-5455 | F: (203) 880-9695





Drawn By:	MDM
Checked By:	KMS
Project #:	2008001
Plan Date:	07/26/21
Scale:	1" = 150'


Project: **EXCAVATION/ FILLING PERMIT APPLICATION**
 10 & 36 MAIN STREET
 MONROE, CONNECTICUT

Sheet Title: **REGULATED AREA MAP**


SHEET #: **FIG. 5**



Slopes Table				
Number	Minimum Slope	Maximum Slope	Color	Area
1	0.00%	10.00%		343209.84
2	10.00%	15.00%		62739.07
3	15.00%	25.00%		61398.43
4	25.00%	25000.00%		145981.52



Rev. #:	Date	Description



 501 Main Street, Monroe, CT 06468
 T: (203) 880-5455 | F: (203) 880-9695

Drawn By: MDM
 Checked By: KMS
 Project #: 2008001
 Plan Date: 07/26/21
 Scale: 1" = 150'

Project: EXCAVATION/ FILLING PERMIT
 APPLICATION
 10 & 36 MAIN STREET
 MONROE, CONNECTICUT

Sheet Title:
 SLOPE AREA MAP

SHEET #:
 FIG. 6



Elevations Table

Number	Minimum Elevation	Maximum Elevation	Color	Area
1	-30.000	-20.000	Dark Blue	2837.34
2	-20.000	-10.000	Blue	7544.78
3	-10.000	0.000	Cyan	87911.10
4	0.000	10.000	Light Green	209601.82
5	10.000	20.000	Bright Green	173381.84
6	20.000	30.000	Medium Green	62615.63
7	30.000	40.000	Dark Green	470.38



Rev. #:	Date	Description

SOLLI
ENGINEERING
501 Main Street, Monroe, CT 06468
T: (203) 880-5455 | F: (203) 880-9695

Drawn By: AWC
Checked By: KMS
Project #: 2008001
Plan Date: 07/26/21
Scale: 1" = 150'

Project: EXCAVATION/ FILLING PERMIT
APPLICATION
10 & 36 MAIN STREET
MONROE, CONNECTICUT

Sheet Title:
CUT/FILL EXHIBIT

SHEET #:
FIG. 7






APPENDIX B
HYDROLOGY


Existing Drainage Area Map (DA-1)
Proposed Drainage Area Map (DA-2)
NOAA Atlas Precipitation Data
Watershed Model Schematic
Hydraflow Stormwater Analysis
Hydraflow Return Period Recap Report
Hydraflow Summary Reports
Hydraflow Stormwater Pond Report
Curve Number Calculations
Time of Concentration Calculations
Water Quality Calculations

GENERAL NOTES


1. THE STORMWATER MANAGEMENT PLAN AND DESIGN IS INTENDED TO BE IN COMPLIANCE WITH THE 2000 CONNECTICUT DEPARTMENT OF TRANSPORTATION (CTDOT) DRAINAGE MANUAL AND THE 2004 CONNECTICUT STORMWATER QUALITY MANUAL.
2. STORMWATER RUNOFF ANALYSIS WAS CALCULATED USING THE SCS TR-55 METHODOLOGY.
3. PRE-EXISTING CONDITIONS WERE EVALUATED FOR THE DRAINAGE CALCULATIONS.

LEGEND

-  PROPERTY LINE
-  LIMITS OF EXISTING DRAINAGE AREA
-  FLOW PATH
-  HYDROLOGIC SOIL GROUP
-  SOIL BOUNDARY LINE



Rev. #:	Date	Description



SOLLI ENGINEERING
 501 Main Street, Monroe, CT 06468 T: (203) 880-5455 F: (203) 880-9695
 331 Newbury Street, Boston, MA 02115 T: (617) 203-3160 F: (203) 880-9695

Drawn By:	CJP	Kevin Solli, P.E. CT 25759
Checked By:	LAM	
Approved By:	KMS	
Project #:	2008001	
Plan Date:	07/26/21	
Scale:	1" = 50'	

EXCAVATION/FILLING PERMIT APPLICATION
 10 & 36 MAIN STREET
 MONROE, CONNECTICUT






Sheet Title:	EXISTING DRAINAGE AREA MAP	Sheet #:	DA-1
--------------	----------------------------	----------	------


Jul 27, 2021 - 10:02am Anthony
 X:\SE Files\Project Data\2021\2008001 - 10 & 36 Main Street - Monroe, CT\Cadd Data\Excavation and Fill Permit\2008001-DA-1.dwg

GENERAL NOTES

1. THE STORMWATER MANAGEMENT PLAN AND DESIGN IS INTENDED TO BE IN COMPLIANCE WITH THE 2000 CONNECTICUT DEPARTMENT OF TRANSPORTATION (CTDOT) DRAINAGE MANUAL AND THE 2004 CONNECTICUT STORMWATER QUALITY MANUAL.
2. STORMWATER RUNOFF ANALYSIS WAS CALCULATED USING THE SCS TR-55 METHODOLOGY.

LEGEND

-  PROPERTY LINE
-  LIMITS OF EXISTING DRAINAGE AREA
-  FLOW PATH
-  HYDROLOGIC SOIL GROUP
-  SOIL BOUNDARY LINE




PROPOSED DRAINAGE AREA 1C (PDA-1C)
 HYDROLOGIC SOIL GROUP A/B
 TOTAL DRAINAGE AREA = 1.01 AC
 IMPERVIOUS AREA = 0.01 AC
 OPEN SPACE (GOOD, A) = 0.68 AC
 OPEN SPACE (GOOD, B) = 0.32 AC
 CURVE NUMBER = 47
 TIME OF CONCENTRATION = 10.8 MIN.

PROPOSED DRAINAGE AREA 1A (PDA-1A)
 HYDROLOGIC SOIL GROUP A/B
 TOTAL DRAINAGE AREA = 12.03 AC
 IMPERVIOUS AREA = 0.29 AC
 OPEN SPACE (GOOD, A) = 0.53 AC
 OPEN SPACE (GOOD, B) = 11.21 AC
 CURVE NUMBER = 61
 TIME OF CONCENTRATION = 26.6 MIN.

PROPOSED DRAINAGE AREA 1B (PDA-1B)
 HYDROLOGIC SOIL GROUP A/B
 TOTAL DRAINAGE AREA = 1.81 AC
 IMPERVIOUS AREA = 0.02 AC
 OPEN SPACE (GOOD, A) = 0.27 AC
 OPEN SPACE (GOOD, B) = 1.52 AC
 CURVE NUMBER = 58
 TIME OF CONCENTRATION = 10.5 MIN.

Rev. #:	Date	Description



SOLLI ENGINEERING
 501 Main Street, Monroe, CT 06468 T: (203) 880-5455 F: (203) 880-9695
 331 Newbury Street, Boston, MA 02115 T: (617) 203-3160 F: (203) 880-9695

Drawn By:	CJP	Kevin Solli, P.E. CT 25759
Checked By:	LAM	
Approved By:	KMS	
Project #:	2008001	
Plan Date:	07/26/21	
Scale:	1" = 50'	

EXCAVATION/FILLING PERMIT APPLICATION
 10 & 36 MAIN STREET
 MONROE, CONNECTICUT

Sheet Title:	PROPOSED DRAINAGE AREA MAP	Sheet #:	DA-2
--------------	----------------------------	----------	------

Jul 27, 2021 - 10:02am Anthony
 X:\SE Files\Project Data\2020\2008001 - 10 & 36 Main Street - Monroe, CT\Cadd Data\Excavation and Fill Permit\20200801-JM-1.dwg



NOAA Atlas 14, Volume 10, Version 3
Location name: Monroe, Connecticut, USA*
Latitude: 41.2987°, Longitude: -73.2479°
Elevation: 346.16 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerials](#)

PF tabular





PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.363 (0.277-0.464)	0.425 (0.324-0.544)	0.526 (0.400-0.676)	0.610 (0.462-0.787)	0.726 (0.534-0.968)	0.813 (0.587-1.10)	0.904 (0.635-1.26)	1.00 (0.673-1.43)	1.15 (0.742-1.67)	1.26 (0.799-1.87)
10-min	0.514 (0.392-0.658)	0.602 (0.459-0.771)	0.745 (0.567-0.959)	0.864 (0.654-1.12)	1.03 (0.756-1.37)	1.15 (0.831-1.56)	1.28 (0.900-1.79)	1.42 (0.954-2.02)	1.63 (1.05-2.37)	1.79 (1.13-2.65)
15-min	0.604 (0.462-0.774)	0.708 (0.540-0.907)	0.877 (0.667-1.13)	1.02 (0.770-1.31)	1.21 (0.889-1.61)	1.36 (0.978-1.84)	1.51 (1.06-2.10)	1.68 (1.12-2.38)	1.91 (1.24-2.79)	2.10 (1.33-3.12)
30-min	0.840 (0.642-1.08)	0.984 (0.751-1.26)	1.22 (0.927-1.57)	1.41 (1.07-1.83)	1.68 (1.24-2.24)	1.89 (1.36-2.55)	2.10 (1.47-2.91)	2.32 (1.55-3.29)	2.62 (1.70-3.82)	2.86 (1.81-4.23)
60-min	1.08 (0.822-1.38)	1.26 (0.961-1.62)	1.56 (1.19-2.01)	1.81 (1.37-2.34)	2.15 (1.58-2.86)	2.42 (1.74-3.26)	2.68 (1.87-3.71)	2.96 (1.98-4.19)	3.33 (2.15-4.85)	3.61 (2.29-5.35)
2-hr	1.39 (1.07-1.77)	1.64 (1.26-2.09)	2.05 (1.57-2.61)	2.38 (1.81-3.05)	2.84 (2.10-3.77)	3.19 (2.31-4.30)	3.56 (2.51-4.92)	3.95 (2.66-5.57)	4.52 (2.93-6.54)	4.97 (3.16-7.31)
3-hr	1.61 (1.24-2.04)	1.90 (1.46-2.41)	2.38 (1.83-3.03)	2.78 (2.12-3.55)	3.33 (2.47-4.40)	3.74 (2.72-5.02)	4.17 (2.96-5.78)	4.66 (3.14-6.55)	5.37 (3.49-7.74)	5.95 (3.78-8.72)
6-hr	2.02 (1.57-2.54)	2.41 (1.87-3.04)	3.05 (2.36-3.85)	3.58 (2.75-4.54)	4.31 (3.22-5.67)	4.86 (3.56-6.50)	5.44 (3.89-7.51)	6.11 (4.13-8.52)	7.10 (4.63-10.2)	7.93 (5.06-11.5)
12-hr	2.48 (1.94-3.10)	2.99 (2.34-3.75)	3.83 (2.98-4.81)	4.53 (3.50-5.70)	5.48 (4.12-7.17)	6.20 (4.57-8.25)	6.96 (5.01-9.57)	7.85 (5.33-10.9)	9.18 (6.01-13.1)	10.3 (6.59-14.9)
24-hr	2.91 (2.29-3.62)	3.56 (2.80-4.43)	4.63 (3.62-5.77)	5.51 (4.29-6.90)	6.72 (5.09-8.76)	7.62 (5.67-10.1)	8.60 (6.24-11.8)	9.77 (6.66-13.5)	11.6 (7.59-16.4)	13.1 (8.40-18.8)
2-day	3.28 (2.59-4.05)	4.07 (3.22-5.03)	5.37 (4.23-6.65)	6.45 (5.05-8.02)	7.94 (6.05-10.3)	9.02 (6.76-11.9)	10.2 (7.50-14.0)	11.7 (8.01-16.1)	14.1 (9.27-19.8)	16.2 (10.4-23.0)
3-day	3.57 (2.83-4.39)	4.44 (3.52-5.46)	5.86 (4.63-7.23)	7.04 (5.53-8.72)	8.66 (6.63-11.2)	9.85 (7.41-13.0)	11.2 (8.23-15.3)	12.8 (8.78-17.5)	15.5 (10.2-21.6)	17.7 (11.4-25.2)
4-day	3.84 (3.06-4.70)	4.76 (3.78-5.83)	6.26 (4.96-7.69)	7.50 (5.91-9.26)	9.22 (7.07-11.9)	10.5 (7.89-13.8)	11.9 (8.75-16.2)	13.6 (9.33-18.5)	16.4 (10.8-22.8)	18.8 (12.1-26.6)
7-day	4.61 (3.69-5.61)	5.61 (4.48-6.84)	7.25 (5.77-8.86)	8.61 (6.82-10.6)	10.5 (8.06-13.4)	11.9 (8.96-15.5)	13.4 (9.85-18.0)	15.2 (10.5-20.6)	18.0 (12.0-25.0)	20.5 (13.3-28.9)
10-day	5.35 (4.30-6.50)	6.41 (5.14-7.79)	8.13 (6.50-9.91)	9.56 (7.60-11.7)	11.5 (8.89-14.7)	13.0 (9.82-16.8)	14.6 (10.7-19.5)	16.4 (11.4-22.1)	19.2 (12.8-26.6)	21.6 (14.0-30.3)
20-day	7.62 (6.16-9.19)	8.78 (7.08-10.6)	10.7 (8.58-12.9)	12.2 (9.79-14.9)	14.4 (11.1-18.1)	16.0 (12.1-20.4)	17.7 (13.0-23.3)	19.6 (13.6-26.2)	22.2 (14.8-30.5)	24.4 (15.8-33.9)
30-day	9.48 (7.69-11.4)	10.7 (8.68-12.9)	12.7 (10.3-15.3)	14.4 (11.5-17.4)	16.7 (12.9-20.8)	18.4 (13.9-23.3)	20.2 (14.8-26.2)	22.1 (15.4-29.3)	24.6 (16.4-33.5)	26.5 (17.3-36.8)
45-day	11.8 (9.58-14.1)	13.1 (10.6-15.7)	15.2 (12.3-18.3)	17.0 (13.7-20.5)	19.4 (15.1-24.0)	21.3 (16.1-26.7)	23.2 (16.9-29.8)	25.0 (17.5-33.1)	27.4 (18.4-37.2)	29.2 (19.0-40.3)
60-day	13.7 (11.2-16.3)	15.0 (12.3-17.9)	17.3 (14.0-20.7)	19.1 (15.4-23.0)	21.7 (16.9-26.7)	23.7 (18.0-29.6)	25.6 (18.7-32.7)	27.5 (19.3-36.2)	29.8 (20.1-40.4)	31.5 (20.6-43.4)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical


PDS-based depth-duration-frequency (DDF) curves
Latitude: 41.2987°, Longitude: -73.2479°




[Back to Top](#)

Maps & aerials

Small scale terrain




Large scale terrain



Large scale map



Large scale aerial



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)



NOAA Atlas 14, Volume 10, Version 3
Location name: Monroe, Connecticut, USA*
Latitude: 41.2987°, Longitude: -73.2479°
Elevation: 346.16 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps & aerials](#)

PF tabular


PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches/hour)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	4.36 (3.32-5.57)	5.10 (3.89-6.53)	6.31 (4.80-8.11)	7.32 (5.54-9.44)	8.71 (6.41-11.6)	9.76 (7.04-13.2)	10.8 (7.62-15.1)	12.0 (8.08-17.1)	13.8 (8.90-20.1)	15.1 (9.59-22.4)
10-min	3.08 (2.35-3.95)	3.61 (2.75-4.63)	4.47 (3.40-5.75)	5.18 (3.92-6.69)	6.17 (4.54-8.23)	6.91 (4.99-9.37)	7.69 (5.40-10.7)	8.54 (5.72-12.1)	9.75 (6.31-14.2)	10.7 (6.79-15.9)
15-min	2.42 (1.85-3.10)	2.83 (2.16-3.63)	3.51 (2.67-4.51)	4.07 (3.08-5.25)	4.84 (3.56-6.45)	5.42 (3.91-7.35)	6.03 (4.24-8.40)	6.70 (4.49-9.50)	7.65 (4.95-11.1)	8.42 (5.33-12.5)
30-min	1.68 (1.28-2.15)	1.97 (1.50-2.52)	2.44 (1.85-3.13)	2.83 (2.14-3.65)	3.36 (2.47-4.48)	3.77 (2.72-5.10)	4.19 (2.93-5.81)	4.63 (3.11-6.57)	5.24 (3.39-7.63)	5.72 (3.62-8.47)
60-min	1.08 (0.822-1.38)	1.26 (0.961-1.62)	1.56 (1.19-2.01)	1.81 (1.37-2.34)	2.15 (1.58-2.86)	2.42 (1.74-3.26)	2.68 (1.87-3.71)	2.96 (1.98-4.19)	3.33 (2.15-4.85)	3.61 (2.29-5.35)
2-hr	0.696 (0.535-0.886)	0.820 (0.630-1.04)	1.02 (0.782-1.31)	1.19 (0.906-1.53)	1.42 (1.05-1.88)	1.60 (1.16-2.15)	1.78 (1.25-2.46)	1.98 (1.33-2.79)	2.26 (1.47-3.27)	2.49 (1.58-3.66)
3-hr	0.534 (0.412-0.678)	0.632 (0.487-0.802)	0.793 (0.609-1.01)	0.925 (0.707-1.18)	1.11 (0.822-1.46)	1.25 (0.907-1.67)	1.39 (0.986-1.92)	1.55 (1.05-2.18)	1.79 (1.16-2.58)	1.98 (1.26-2.90)
6-hr	0.337 (0.262-0.424)	0.402 (0.312-0.507)	0.509 (0.394-0.643)	0.598 (0.460-0.758)	0.720 (0.538-0.947)	0.811 (0.595-1.09)	0.908 (0.649-1.25)	1.02 (0.690-1.42)	1.19 (0.773-1.70)	1.32 (0.844-1.93)
12-hr	0.206 (0.161-0.258)	0.248 (0.194-0.311)	0.318 (0.247-0.399)	0.376 (0.290-0.473)	0.455 (0.342-0.595)	0.514 (0.379-0.685)	0.577 (0.415-0.794)	0.652 (0.442-0.903)	0.762 (0.498-1.09)	0.855 (0.547-1.24)
24-hr	0.121 (0.095-0.151)	0.148 (0.117-0.184)	0.193 (0.151-0.240)	0.230 (0.179-0.287)	0.280 (0.212-0.365)	0.318 (0.236-0.421)	0.358 (0.260-0.492)	0.407 (0.277-0.561)	0.482 (0.316-0.682)	0.546 (0.350-0.783)
2-day	0.068 (0.054-0.084)	0.085 (0.067-0.105)	0.112 (0.088-0.139)	0.134 (0.105-0.167)	0.165 (0.126-0.214)	0.188 (0.141-0.249)	0.213 (0.156-0.293)	0.244 (0.167-0.334)	0.293 (0.193-0.413)	0.336 (0.217-0.480)
3-day	0.050 (0.039-0.061)	0.062 (0.049-0.076)	0.081 (0.064-0.100)	0.098 (0.077-0.121)	0.120 (0.092-0.156)	0.137 (0.103-0.181)	0.155 (0.114-0.213)	0.178 (0.122-0.243)	0.215 (0.141-0.300)	0.246 (0.159-0.350)
4-day	0.040 (0.032-0.049)	0.050 (0.039-0.061)	0.065 (0.052-0.080)	0.078 (0.062-0.097)	0.096 (0.074-0.124)	0.109 (0.082-0.143)	0.124 (0.091-0.169)	0.142 (0.097-0.193)	0.170 (0.112-0.238)	0.195 (0.126-0.277)
7-day	0.027 (0.022-0.033)	0.033 (0.027-0.041)	0.043 (0.034-0.053)	0.051 (0.041-0.063)	0.062 (0.048-0.080)	0.071 (0.053-0.092)	0.080 (0.059-0.107)	0.091 (0.062-0.122)	0.107 (0.071-0.149)	0.122 (0.079-0.172)
10-day	0.022 (0.018-0.027)	0.027 (0.021-0.032)	0.034 (0.027-0.041)	0.040 (0.032-0.049)	0.048 (0.037-0.061)	0.054 (0.041-0.070)	0.061 (0.045-0.081)	0.069 (0.047-0.092)	0.080 (0.053-0.111)	0.090 (0.058-0.126)
20-day	0.016 (0.013-0.019)	0.018 (0.015-0.022)	0.022 (0.018-0.027)	0.026 (0.020-0.031)	0.030 (0.023-0.038)	0.033 (0.025-0.043)	0.037 (0.027-0.048)	0.041 (0.028-0.055)	0.046 (0.031-0.064)	0.051 (0.033-0.071)
30-day	0.013 (0.011-0.016)	0.015 (0.012-0.018)	0.018 (0.014-0.021)	0.020 (0.016-0.024)	0.023 (0.018-0.029)	0.026 (0.019-0.032)	0.028 (0.020-0.036)	0.031 (0.021-0.041)	0.034 (0.023-0.047)	0.037 (0.024-0.051)
45-day	0.011 (0.009-0.013)	0.012 (0.010-0.014)	0.014 (0.011-0.017)	0.016 (0.013-0.019)	0.018 (0.014-0.022)	0.020 (0.015-0.025)	0.021 (0.016-0.028)	0.023 (0.016-0.031)	0.025 (0.017-0.034)	0.027 (0.018-0.037)
60-day	0.009 (0.008-0.011)	0.010 (0.009-0.012)	0.012 (0.010-0.014)	0.013 (0.011-0.016)	0.015 (0.012-0.019)	0.016 (0.012-0.021)	0.018 (0.013-0.023)	0.019 (0.013-0.025)	0.021 (0.014-0.028)	0.022 (0.014-0.030)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.


[Back to Top](#)

PF graphical

PDS-based intensity-duration-frequency (IDF) curves
Latitude: 41.2987°, Longitude: -73.2479°



Average recurrence interval (years)
1
2
5
10
25
50
100
200
500
1000




Duration
5-min
10-min
15-min
30-min
60-min
2-hr
3-hr
6-hr
12-hr
24-hr
2-day
3-day
4-day
7-day
10-day
20-day
30-day
45-day
60-day


[Back to Top](#)

Maps & aerials

Small scale terrain




Large scale terrain



Large scale map



Large scale aerial




[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)

Watershed Model Schematic

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022



Legend

Hyd. Origin	Description
1	SCS Runoff EDA-1
2	SCS Runoff PDA-1A
3	SCS Runoff PDA-1B
4	SCS Runoff PDA-1C
5	Reservoir Stormwater Basin #1
6	Combine Overall PDA

Hydrograph Return Period Recap

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	SCS Runoff	-----	-----	13.79	-----	23.65	32.43	45.06	54.79	65.55	EDA-1
2	SCS Runoff	-----	-----	4.054	-----	9.017	13.89	21.37	27.36	34.18	PDA-1A
3	SCS Runoff	-----	-----	0.547	-----	1.480	2.421	3.885	5.064	6.427	PDA-1B
4	SCS Runoff	-----	-----	0.022	-----	0.190	0.462	1.023	1.517	2.116	PDA-1C
5	Reservoir	2	-----	2.303	-----	7.132	9.849	17.22	23.88	28.36	Stormwater Basin #1
6	Combine	3, 4, 5	-----	2.498	-----	7.798	10.89	19.02	26.67	31.85	Overall PDA

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	13.79	1	734	61,838	-----	-----	-----	EDA-1	
2	SCS Runoff	4.054	1	747	26,403	-----	-----	-----	PDA-1A	
3	SCS Runoff	0.547	1	733	3,189	-----	-----	-----	PDA-1B	
4	SCS Runoff	0.022	1	753	505	-----	-----	-----	PDA-1C	
5	Reservoir	2.303	1	766	22,513	2	295.20	6,247	Stormwater Basin #1	
6	Combine	2.498	1	766	26,207	3, 4, 5	-----	-----	Overall PDA	
2008001-Hydrology.gpw					Return Period: 2 Year			Friday, 07 / 23 / 2021		

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	23.65	1	733	102,162	-----	-----	-----	EDA-1	
2	SCS Runoff	9.017	1	742	50,724	-----	-----	-----	PDA-1A	
3	SCS Runoff	1.480	1	730	6,495	-----	-----	-----	PDA-1B	
4	SCS Runoff	0.190	1	739	1,541	-----	-----	-----	PDA-1C	
5	Reservoir	7.132	1	755	46,833	2	295.95	9,274	Stormwater Basin #1	
6	Combine	7.798	1	753	54,870	3, 4, 5	-----	-----	Overall PDA	
2008001-Hydrology.gpw					Return Period: 5 Year			Friday, 07 / 23 / 2021		

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	32.43	1	733	138,432	-----	-----	-----	EDA-1	
2	SCS Runoff	13.89	1	741	74,162	-----	-----	-----	PDA-1A	
3	SCS Runoff	2.421	1	729	9,761	-----	-----	-----	PDA-1B	
4	SCS Runoff	0.462	1	733	2,720	-----	-----	-----	PDA-1C	
5	Reservoir	9.849	1	757	70,272	2	296.83	13,671	Stormwater Basin #1	
6	Combine	10.89	1	750	82,753	3, 4, 5	-----	-----	Overall PDA	
2008001-Hydrology.gpw					Return Period: 10 Year			Friday, 07 / 23 / 2021		

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	45.06	1	733	191,410	-----	-----	-----	EDA-1	
2	SCS Runoff	21.37	1	740	110,103	-----	-----	-----	PDA-1A	
3	SCS Runoff	3.885	1	729	14,853	-----	-----	-----	PDA-1B	
4	SCS Runoff	1.023	1	730	4,726	-----	-----	-----	PDA-1C	
5	Reservoir	17.22	1	752	106,213	2	297.94	20,311	Stormwater Basin #1	
6	Combine	19.02	1	752	125,792	3, 4, 5	-----	-----	Overall PDA	
2008001-Hydrology.gpw					Return Period: 25 Year			Friday, 07 / 23 / 2021		

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	54.79	1	732	232,498	-----	-----	-----	EDA-1	
2	SCS Runoff	27.36	1	739	138,970	-----	-----	-----	PDA-1A	
3	SCS Runoff	5.064	1	729	18,991	-----	-----	-----	PDA-1B	
4	SCS Runoff	1.517	1	730	6,454	-----	-----	-----	PDA-1C	
5	Reservoir	23.88	1	749	135,079	2	298.28	22,719	Stormwater Basin #1	
6	Combine	26.67	1	748	160,525	3, 4, 5	-----	-----	Overall PDA	
2008001-Hydrology.gpw					Return Period: 50 Year			Friday, 07 / 23 / 2021		

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® by Autodesk, Inc. v2022


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SCS Runoff	65.55	1	732	278,440	-----	-----	-----	EDA-1	
2	SCS Runoff	34.18	1	739	172,005	-----	-----	-----	PDA-1A	
3	SCS Runoff	6.427	1	728	23,765	-----	-----	-----	PDA-1B	
4	SCS Runoff	2.116	1	729	8,525	-----	-----	-----	PDA-1C	
5	Reservoir	28.36	1	751	168,115	2	298.82	26,615	Stormwater Basin #1	
6	Combine	31.85	1	746	200,405	3, 4, 5	-----	-----	Overall PDA	
2008001-Hydrology.gpw					Return Period: 100 Year			Friday, 07 / 23 / 2021		

Hydrograph Report

Hyd. No. 1

EDA-1

Hydrograph type	= SCS Runoff	Peak discharge	= 65.55 cfs
Storm frequency	= 100 yrs	Time to peak	= 12.20 hrs
Time interval	= 1 min	Hyd. volume	= 278,440 cuft
Drainage area	= 14.850 ac	Curve number	= 72
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 17.50 min
Total precip.	= 8.60 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484




Hydrograph Report

Hyd. No. 2

PDA-1A

Hydrograph type	= SCS Runoff	Peak discharge	= 34.18 cfs
Storm frequency	= 100 yrs	Time to peak	= 12.32 hrs
Time interval	= 1 min	Hyd. volume	= 172,005 cuft
Drainage area	= 12.030 ac	Curve number	= 61
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 26.60 min
Total precip.	= 8.60 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484




Hydrograph Report

Hyd. No. 3

PDA-1B

Hydrograph type	= SCS Runoff	Peak discharge	= 6.427 cfs
Storm frequency	= 100 yrs	Time to peak	= 12.13 hrs
Time interval	= 1 min	Hyd. volume	= 23,765 cuft
Drainage area	= 1.810 ac	Curve number	= 58
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.50 min
Total precip.	= 8.60 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484




Hydrograph Report

Hyd. No. 4

PDA-1C

Hydrograph type	= SCS Runoff	Peak discharge	= 2.116 cfs
Storm frequency	= 100 yrs	Time to peak	= 12.15 hrs
Time interval	= 1 min	Hyd. volume	= 8,525 cuft
Drainage area	= 1.010 ac	Curve number	= 47
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 10.80 min
Total precip.	= 8.60 in	Distribution	= Type III
Storm duration	= 24 hrs	Shape factor	= 484




Hydrograph Report

Hyd. No. 5

Stormwater Basin #1

Hydrograph type	= Reservoir	Peak discharge	= 28.36 cfs
Storm frequency	= 100 yrs	Time to peak	= 12.52 hrs
Time interval	= 1 min	Hyd. volume	= 168,115 cuft
Inflow hyd. No.	= 2 - PDA-1A	Max. Elevation	= 298.82 ft
Reservoir name	= Stormwater Basin #1	Max. Storage	= 26,615 cuft

Storage Indication method used.




Hydrograph Report

Hyd. No. 6

Overall PDA

Hydrograph type = Combine
Storm frequency = 100 yrs
Time interval = 1 min
Inflow hyds. = 3, 4, 5

Peak discharge = 31.85 cfs
Time to peak = 12.43 hrs
Hyd. volume = 200,405 cuft
Contrib. drain. area = 2.820 ac



Hydrograph Report

Hyd. No. 5

Stormwater Basin #1

Hydrograph type	= Reservoir	Peak discharge	= 28.36 cfs
Storm frequency	= 100 yrs	Time to peak	= 12.52 hrs
Time interval	= 1 min	Hyd. volume	= 168,115 cuft
Inflow hyd. No.	= 2 - PDA-1A	Reservoir name	= Stormwater Basin
Max. Elevation	= 298.82 ft	Max. Storage	= 26,615 cuft

Storage Indication method used.

Hydrograph Discharge Table

(Printed values >= 1.00% of Qp. Print interval = 5)

Time (hrs)	Inflow cfs	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	Outflow cfs
11.33	1.889	294.76	0.413	0.395	----	----	----	----	----	----	----	0.395
11.42	2.138	294.90	0.839	0.839	----	----	----	----	----	----	----	0.839
11.50	2.429	295.01	1.323	1.319	----	----	----	----	----	----	----	1.319
11.58	2.795	295.09	1.760	1.728	----	----	----	----	----	----	----	1.729
11.67	3.387	295.17	2.229	2.174	----	----	----	----	----	----	----	2.174
11.75	4.408	295.28	2.880	2.809	----	----	----	----	----	----	----	2.809
11.83	6.081	295.42	3.784	3.734	----	----	----	----	----	----	----	3.734
11.92	8.504	295.63	5.238	5.173	----	----	----	----	----	----	----	5.173
12.00	12.46	295.94	7.148	7.096	----	----	----	----	----	----	----	7.096
12.08	19.14	296.41	8.822	8.786	----	----	----	----	----	----	----	8.786
12.17	26.57	297.16	10.62	10.62	----	----	----	----	----	----	----	10.62
12.25	32.65	297.99	18.09	9.742	----	----	8.349	----	----	----	----	18.09
12.33	34.11	298.44	25.78	6.221	----	----	19.56	----	----	----	----	25.78
12.42	32.35	298.71	27.73	5.008	----	----	22.72	----	----	----	----	27.73
12.50	28.85	298.81	28.36	4.644	----	----	23.72	----	----	----	----	28.36
12.58	24.02	298.74	27.95	4.883	----	----	23.06	----	----	----	----	27.94
12.67	18.56	298.50	26.28	5.897	----	----	20.39	----	----	----	----	26.28
12.75	14.05	298.16	21.64	8.400	----	----	13.24	----	----	----	----	21.64
12.83	11.19	297.89	16.18	10.24	----	----	5.937	----	----	----	----	16.17
12.92	9.194	297.68	12.79	10.82	----	----	1.971	----	----	----	----	12.79

Continues on next page...

Hydrograph Discharge Table

Time (hrs)	Inflow cfs	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	Outflow cfs
13.00	7.824	297.51	11.42	11.30	----	----	0.092	----	----	----	----	11.39
13.08	6.925	297.32	10.98	10.98	----	----	----	----	----	----	----	10.98
13.17	6.340	297.12	10.53	10.53	----	----	----	----	----	----	----	10.53
13.25	5.913	296.90	10.05	10.03	----	----	----	----	----	----	----	10.03
13.33	5.571	296.66	9.481	9.445	----	----	----	----	----	----	----	9.445
13.42	5.305	296.44	8.894	8.870	----	----	----	----	----	----	----	8.870
13.50	5.097	296.24	8.325	8.285	----	----	----	----	----	----	----	8.285
13.58	4.931	296.06	7.661	7.661	----	----	----	----	----	----	----	7.661
13.67	4.790	295.90	6.985	6.902	----	----	----	----	----	----	----	6.902
13.75	4.657	295.77	6.163	6.101	----	----	----	----	----	----	----	6.101
13.83	4.522	295.68	5.588	5.497	----	----	----	----	----	----	----	5.497
13.92	4.386	295.62	5.133	5.076	----	----	----	----	----	----	----	5.076
14.00	4.249	295.57	4.812	4.771	----	----	----	----	----	----	----	4.771
14.08	4.111	295.54	4.566	4.533	----	----	----	----	----	----	----	4.533
14.17	3.978	295.51	4.362	4.336	----	----	----	----	----	----	----	4.336
14.25	3.856	295.48	4.195	4.165	----	----	----	----	----	----	----	4.165
14.33	3.750	295.46	4.054	4.017	----	----	----	----	----	----	----	4.017
14.42	3.659	295.44	3.932	3.889	----	----	----	----	----	----	----	3.889
14.50	3.578	295.43	3.826	3.778	----	----	----	----	----	----	----	3.778
14.58	3.506	295.41	3.734	3.682	----	----	----	----	----	----	----	3.682
14.67	3.438	295.40	3.652	3.596	----	----	----	----	----	----	----	3.596
14.75	3.371	295.39	3.582	3.523	----	----	----	----	----	----	----	3.523
14.83	3.304	295.38	3.514	3.453	----	----	----	----	----	----	----	3.453
14.92	3.237	295.37	3.447	3.384	----	----	----	----	----	----	----	3.384
15.00	3.169	295.36	3.380	3.316	----	----	----	----	----	----	----	3.316
15.08	3.100	295.35	3.313	3.247	----	----	----	----	----	----	----	3.247
15.17	3.031	295.34	3.247	3.179	----	----	----	----	----	----	----	3.179
15.25	2.962	295.32	3.180	3.110	----	----	----	----	----	----	----	3.110

Continues on next page...

Hydrograph Discharge Table

Time (hrs)	Inflow cfs	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	Outflow cfs
15.33	2.893	295.31	3.113	3.041	----	----	----	----	----	----	----	3.041
15.42	2.823	295.30	3.046	2.972	----	----	----	----	----	----	----	2.972
15.50	2.752	295.29	2.974	2.901	----	----	----	----	----	----	----	2.901
15.58	2.682	295.28	2.902	2.830	----	----	----	----	----	----	----	2.830
15.67	2.611	295.27	2.830	2.759	----	----	----	----	----	----	----	2.759
15.75	2.539	295.26	2.757	2.688	----	----	----	----	----	----	----	2.688
15.83	2.468	295.25	2.685	2.617	----	----	----	----	----	----	----	2.617
15.92	2.396	295.24	2.612	2.545	----	----	----	----	----	----	----	2.545
16.00	2.323	295.22	2.539	2.474	----	----	----	----	----	----	----	2.474
16.08	2.252	295.21	2.466	2.402	----	----	----	----	----	----	----	2.402
16.17	2.183	295.20	2.394	2.331	----	----	----	----	----	----	----	2.330
16.25	2.121	295.19	2.329	2.269	----	----	----	----	----	----	----	2.269
16.33	2.067	295.18	2.268	2.210	----	----	----	----	----	----	----	2.210
16.42	2.021	295.17	2.209	2.155	----	----	----	----	----	----	----	2.155
16.50	1.982	295.16	2.156	2.104	----	----	----	----	----	----	----	2.104
16.58	1.947	295.15	2.107	2.058	----	----	----	----	----	----	----	2.058
16.67	1.915	295.14	2.063	2.016	----	----	----	----	----	----	----	2.016
16.75	1.884	295.14	2.022	1.977	----	----	----	----	----	----	----	1.977
16.83	1.853	295.13	1.984	1.941	----	----	----	----	----	----	----	1.941
16.92	1.821	295.12	1.948	1.906	----	----	----	----	----	----	----	1.906
17.00	1.790	295.12	1.912	1.873	----	----	----	----	----	----	----	1.873
17.08	1.758	295.11	1.878	1.840	----	----	----	----	----	----	----	1.840
17.17	1.727	295.11	1.843	1.807	----	----	----	----	----	----	----	1.807
17.25	1.695	295.10	1.810	1.775	----	----	----	----	----	----	----	1.775
17.33	1.663	295.09	1.777	1.745	----	----	----	----	----	----	----	1.745
17.42	1.631	295.09	1.744	1.713	----	----	----	----	----	----	----	1.713
17.50	1.599	295.08	1.710	1.682	----	----	----	----	----	----	----	1.682
17.58	1.567	295.08	1.676	1.651	----	----	----	----	----	----	----	1.650

Continues on next page...

Hydrograph Discharge Table

Time (hrs)	Inflow cfs	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	Outflow cfs
17.67	1.535	295.07	1.643	1.619	----	----	----	----	----	----	----	1.619
17.75	1.503	295.06	1.609	1.587	----	----	----	----	----	----	----	1.587
17.83	1.471	295.06	1.574	1.555	----	----	----	----	----	----	----	1.555
17.92	1.438	295.05	1.540	1.523	----	----	----	----	----	----	----	1.523
18.00	1.406	295.04	1.506	1.490	----	----	----	----	----	----	----	1.491
18.08	1.374	295.04	1.471	1.458	----	----	----	----	----	----	----	1.458
18.17	1.344	295.03	1.437	1.426	----	----	----	----	----	----	----	1.426
18.25	1.317	295.03	1.404	1.396	----	----	----	----	----	----	----	1.396
18.33	1.295	295.02	1.374	1.367	----	----	----	----	----	----	----	1.367
18.42	1.277	295.01	1.346	1.341	----	----	----	----	----	----	----	1.341
18.50	1.264	295.01	1.322	1.318	----	----	----	----	----	----	----	1.319
18.58	1.252	295.01	1.301	1.299	----	----	----	----	----	----	----	1.299
18.67	1.242	295.00	1.284	1.283	----	----	----	----	----	----	----	1.283
18.75	1.233	295.00	1.269	1.268	----	----	----	----	----	----	----	1.268
18.83	1.223	295.00	1.255	1.255	----	----	----	----	----	----	----	1.255
18.92	1.214	294.99	1.243	1.243	----	----	----	----	----	----	----	1.243
19.00	1.205	294.99	1.232	1.231	----	----	----	----	----	----	----	1.231
19.08	1.195	294.99	1.221	1.221	----	----	----	----	----	----	----	1.221
19.17	1.186	294.99	1.211	1.211	----	----	----	----	----	----	----	1.211
19.25	1.176	294.98	1.201	1.201	----	----	----	----	----	----	----	1.201
19.33	1.167	294.98	1.191	1.191	----	----	----	----	----	----	----	1.191
19.42	1.157	294.98	1.181	1.181	----	----	----	----	----	----	----	1.181
19.50	1.148	294.98	1.171	1.171	----	----	----	----	----	----	----	1.171
19.58	1.138	294.98	1.162	1.162	----	----	----	----	----	----	----	1.162
19.67	1.128	294.97	1.152	1.152	----	----	----	----	----	----	----	1.152
19.75	1.119	294.97	1.143	1.142	----	----	----	----	----	----	----	1.143
19.83	1.109	294.97	1.133	1.133	----	----	----	----	----	----	----	1.133
19.92	1.100	294.97	1.123	1.123	----	----	----	----	----	----	----	1.123

Continues on next page...

Hydrograph Discharge Table

Time (hrs)	Inflow cfs	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	Outflow cfs
20.00	1.090	294.96	1.114	1.114	----	----	----	----	----	----	----	1.114
20.08	1.080	294.96	1.104	1.104	----	----	----	----	----	----	----	1.104
20.17	1.071	294.96	1.095	1.094	----	----	----	----	----	----	----	1.094
20.25	1.061	294.96	1.085	1.085	----	----	----	----	----	----	----	1.085
20.33	1.051	294.96	1.075	1.075	----	----	----	----	----	----	----	1.075
20.42	1.042	294.95	1.066	1.065	----	----	----	----	----	----	----	1.066
20.50	1.032	294.95	1.056	1.056	----	----	----	----	----	----	----	1.056
20.58	1.022	294.95	1.046	1.046	----	----	----	----	----	----	----	1.046
20.67	1.013	294.95	1.037	1.037	----	----	----	----	----	----	----	1.036
20.75	1.003	294.94	1.027	1.027	----	----	----	----	----	----	----	1.027
20.83	0.993	294.94	1.017	1.017	----	----	----	----	----	----	----	1.017
20.92	0.983	294.94	1.007	1.007	----	----	----	----	----	----	----	1.007
21.00	0.973	294.94	0.997	0.997	----	----	----	----	----	----	----	0.998
21.08	0.964	294.93	0.988	0.988	----	----	----	----	----	----	----	0.988
21.17	0.954	294.93	0.978	0.978	----	----	----	----	----	----	----	0.978
21.25	0.944	294.93	0.968	0.968	----	----	----	----	----	----	----	0.968
21.33	0.934	294.93	0.958	0.958	----	----	----	----	----	----	----	0.958
21.42	0.924	294.93	0.949	0.949	----	----	----	----	----	----	----	0.949
21.50	0.915	294.92	0.939	0.939	----	----	----	----	----	----	----	0.939
21.58	0.905	294.92	0.929	0.929	----	----	----	----	----	----	----	0.929
21.67	0.895	294.92	0.919	0.919	----	----	----	----	----	----	----	0.919
21.75	0.885	294.92	0.909	0.909	----	----	----	----	----	----	----	0.909
21.83	0.875	294.91	0.899	0.899	----	----	----	----	----	----	----	0.899
21.92	0.865	294.91	0.889	0.889	----	----	----	----	----	----	----	0.889
22.00	0.855	294.91	0.879	0.879	----	----	----	----	----	----	----	0.880
22.08	0.901	294.91	0.879	0.879	----	----	----	----	----	----	----	0.879
22.17	0.952	294.91	0.896	0.896	----	----	----	----	----	----	----	0.896
22.25	1.008	294.92	0.924	0.924	----	----	----	----	----	----	----	0.924

Continues on next page...

Hydrograph Discharge Table

Time (hrs)	Inflow cfs	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	Outflow cfs
22.33	0.998	294.93	0.953	0.953	----	----	----	----	----	----	----	0.953
22.42	0.969	294.93	0.963	0.963	----	----	----	----	----	----	----	0.963
22.50	0.937	294.93	0.959	0.959	----	----	----	----	----	----	----	0.959
22.58	0.903	294.92	0.946	0.946	----	----	----	----	----	----	----	0.946
22.67	0.866	294.92	0.925	0.925	----	----	----	----	----	----	----	0.925
22.75	0.840	294.91	0.900	0.900	----	----	----	----	----	----	----	0.900
22.83	0.833	294.91	0.878	0.878	----	----	----	----	----	----	----	0.878
22.92	0.825	294.90	0.862	0.862	----	----	----	----	----	----	----	0.862
23.00	0.818	294.90	0.848	0.848	----	----	----	----	----	----	----	0.848
23.08	0.811	294.90	0.838	0.838	----	----	----	----	----	----	----	0.838
23.17	0.803	294.90	0.830	0.829	----	----	----	----	----	----	----	0.829
23.25	0.796	294.89	0.822	0.820	----	----	----	----	----	----	----	0.820
23.33	0.788	294.89	0.814	0.812	----	----	----	----	----	----	----	0.812
23.42	0.781	294.89	0.807	0.804	----	----	----	----	----	----	----	0.804
23.50	0.773	294.89	0.800	0.796	----	----	----	----	----	----	----	0.796
23.58	0.766	294.88	0.793	0.789	----	----	----	----	----	----	----	0.789
23.67	0.758	294.88	0.786	0.781	----	----	----	----	----	----	----	0.781
23.75	0.751	294.88	0.778	0.773	----	----	----	----	----	----	----	0.773
23.83	0.743	294.88	0.771	0.766	----	----	----	----	----	----	----	0.766
23.92	0.736	294.88	0.764	0.758	----	----	----	----	----	----	----	0.758
24.00	0.728	294.87	0.757	0.751	----	----	----	----	----	----	----	0.751
24.08	0.690	294.87	0.747	0.740	----	----	----	----	----	----	----	0.740
24.17	0.602	294.86	0.723	0.713	----	----	----	----	----	----	----	0.713
24.25	0.464	294.85	0.675	0.662	----	----	----	----	----	----	----	0.662
24.33	0.310	294.83	0.601	0.581	----	----	----	----	----	----	----	0.581
24.42	0.187	294.80	0.511	0.485	----	----	----	----	----	----	----	0.485
24.50	0.095	294.77	0.424	0.405	----	----	----	----	----	----	----	0.405
24.58	0.034	294.74	0.339	0.326	----	----	----	----	----	----	----	0.326

Continues on next page...

...End

Pond Report

Pond No. 1 - Stormwater Basin #1

Pond Data

Contours -User-defined contour areas. Conic method used for volume calculation. Begining Elevation = 293.00 ft

Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	293.00	1,951	0	0
1.00	294.00	2,711	2,320	2,320
2.00	295.00	3,567	3,129	5,449
3.00	296.00	4,529	4,038	9,487
4.00	297.00	5,567	5,039	14,526
5.00	298.00	6,713	6,130	20,656
6.00	299.00	7,923	7,309	27,965
7.00	300.00	9,704	8,798	36,763

Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 24.00	18.00	Inactive	0.00
Span (in)	= 24.00	18.00	0.00	0.00
No. Barrels	= 1	1	1	0
Invert El. (ft)	= 294.00	294.50	0.00	0.00
Length (ft)	= 75.00	0.67	0.00	0.00
Slope (%)	= 0.67	0.00	0.00	n/a
N-Value	= .012	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	Yes	No	No

Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 7.33	30.00	Inactive	0.00
Crest El. (ft)	= 297.50	299.00	0.00	0.00
Weir Coeff.	= 3.33	2.60	3.33	3.33
Weir Type	= 1	Broad	---	---
Multi-Stage	= Yes	No	No	No
Exfil.(in/hr)	= 0.000	(by Wet area)		
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).

Stage / Storage / Discharge Table

Stage ft	Storage cuft	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
0.00	0	293.00	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.10	232	293.10	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.20	464	293.20	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.30	696	293.30	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.40	928	293.40	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.50	1,160	293.50	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.60	1,392	293.60	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.70	1,624	293.70	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.80	1,856	293.80	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
0.90	2,088	293.90	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
1.00	2,320	294.00	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
1.10	2,633	294.10	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
1.20	2,946	294.20	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
1.30	3,259	294.30	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
1.40	3,572	294.40	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
1.50	3,885	294.50	0.00	0.00	---	---	0.00	0.00	---	---	---	---	0.000
1.60	4,198	294.60	0.06 ic	0.06 ic	---	---	0.00	0.00	---	---	---	---	0.058
1.70	4,511	294.70	0.22 ic	0.22 ic	---	---	0.00	0.00	---	---	---	---	0.218
1.80	4,824	294.80	0.52 ic	0.49 ic	---	---	0.00	0.00	---	---	---	---	0.490
1.90	5,136	294.90	0.84 ic	0.84 ic	---	---	0.00	0.00	---	---	---	---	0.842
2.00	5,449	295.00	1.27 ic	1.27 ic	---	---	0.00	0.00	---	---	---	---	1.265
2.10	5,853	295.10	1.81 ic	1.78 ic	---	---	0.00	0.00	---	---	---	---	1.778
2.20	6,257	295.20	2.38 ic	2.32 ic	---	---	0.00	0.00	---	---	---	---	2.316
2.30	6,661	295.30	3.03 ic	2.96 ic	---	---	0.00	0.00	---	---	---	---	2.959
2.40	7,065	295.40	3.64 ic	3.59 ic	---	---	0.00	0.00	---	---	---	---	3.586
2.50	7,468	295.50	4.30 ic	4.28 ic	---	---	0.00	0.00	---	---	---	---	4.281
2.60	7,872	295.60	5.01 ic	4.96 ic	---	---	0.00	0.00	---	---	---	---	4.964
2.70	8,276	295.70	5.76 ic	5.65 ic	---	---	0.00	0.00	---	---	---	---	5.654
2.80	8,680	295.80	6.37 ic	6.33 ic	---	---	0.00	0.00	---	---	---	---	6.335
2.90	9,084	295.90	7.00 ic	6.92 ic	---	---	0.00	0.00	---	---	---	---	6.920
3.00	9,487	296.00	7.37 ic	7.37 ic	---	---	0.00	0.00	---	---	---	---	7.368
3.10	9,991	296.10	7.84 ic	7.84 ic	---	---	0.00	0.00	---	---	---	---	7.844
3.20	10,495	296.20	8.17 ic	8.17 ic	---	---	0.00	0.00	---	---	---	---	8.167
3.30	10,999	296.30	8.57 oc	8.47 ic	---	---	0.00	0.00	---	---	---	---	8.469
3.40	11,503	296.40	8.80 oc	8.76 ic	---	---	0.00	0.00	---	---	---	---	8.764

Continues on next page...

Stormwater Basin #1

Stage / Storage / Discharge Table

Stage ft	Storage cuft	Elevation ft	Clv A cfs	Clv B cfs	Clv C cfs	PrfRsr cfs	Wr A cfs	Wr B cfs	Wr C cfs	Wr D cfs	Exfil cfs	User cfs	Total cfs
3.50	12,007	296.50	9.03 oc	9.03 ic	---	---	0.00	0.00	---	---	---	---	9.027
3.60	12,510	296.60	9.35 oc	9.27 ic	---	---	0.00	0.00	---	---	---	---	9.275
3.70	13,014	296.70	9.56 oc	9.55 ic	---	---	0.00	0.00	---	---	---	---	9.550
3.80	13,518	296.80	9.86 oc	9.77 ic	---	---	0.00	0.00	---	---	---	---	9.768
3.90	14,022	296.90	10.05 oc	10.03 ic	---	---	0.00	0.00	---	---	---	---	10.03
4.00	14,526	297.00	10.31 oc	10.25 ic	---	---	0.00	0.00	---	---	---	---	10.25
4.10	15,139	297.10	10.48 oc	10.48 ic	---	---	0.00	0.00	---	---	---	---	10.48
4.20	15,752	297.20	10.72 oc	10.72 ic	---	---	0.00	0.00	---	---	---	---	10.72
4.30	16,365	297.30	10.93 oc	10.93 ic	---	---	0.00	0.00	---	---	---	---	10.93
4.40	16,978	297.40	11.13 oc	11.13 ic	---	---	0.00	0.00	---	---	---	---	11.13
4.50	17,591	297.50	11.35 oc	11.32 ic	---	---	0.00	0.00	---	---	---	---	11.32
4.60	18,204	297.60	11.92 oc	11.15 ic	---	---	0.77	0.00	---	---	---	---	11.92
4.70	18,817	297.70	12.94 oc	10.76 ic	---	---	2.18	0.00	---	---	---	---	12.94
4.80	19,430	297.80	14.56 oc	10.55 ic	---	---	4.01	0.00	---	---	---	---	14.56
4.90	20,043	297.90	16.38 oc	10.20 ic	---	---	6.18	0.00	---	---	---	---	16.38
5.00	20,656	298.00	18.31 oc	9.68 ic	---	---	8.63	0.00	---	---	---	---	18.31
5.10	21,387	298.10	20.33 oc	8.98 ic	---	---	11.34	0.00	---	---	---	---	20.33
5.20	22,118	298.20	22.37 oc	8.07 ic	---	---	14.30	0.00	---	---	---	---	22.37
5.30	22,849	298.30	24.21 oc	7.08 ic	---	---	17.13 s	0.00	---	---	---	---	24.21
5.40	23,580	298.40	25.42 ic	6.45 ic	---	---	18.97 s	0.00	---	---	---	---	25.42
5.50	24,311	298.50	26.28 ic	5.90 ic	---	---	20.38 s	0.00	---	---	---	---	26.28
5.60	25,042	298.60	27.02 ic	5.44 ic	---	---	21.58 s	0.00	---	---	---	---	27.02
5.70	25,773	298.70	27.68 ic	5.04 ic	---	---	22.64 s	0.00	---	---	---	---	27.68
5.80	26,504	298.80	28.28 ic	4.69 ic	---	---	23.59 s	0.00	---	---	---	---	28.28
5.90	27,234	298.90	28.83 ic	4.38 ic	---	---	24.45 s	0.00	---	---	---	---	28.83
6.00	27,965	299.00	29.35 ic	4.12 ic	---	---	25.24 s	0.00	---	---	---	---	29.35
6.10	28,845	299.10	29.84 ic	3.87 ic	---	---	25.96 s	2.47	---	---	---	---	32.30
6.20	29,725	299.20	30.31 ic	3.66 ic	---	---	26.64 s	6.98	---	---	---	---	37.28
6.30	30,605	299.30	30.75 ic	3.47 ic	---	---	27.28 s	12.82	---	---	---	---	43.57
6.40	31,484	299.40	31.18 ic	3.29 ic	---	---	27.88 s	19.73	---	---	---	---	50.91
6.50	32,364	299.50	31.60 ic	3.14 ic	---	---	28.46 s	27.58	---	---	---	---	59.17
6.60	33,244	299.60	32.00 ic	2.99 ic	---	---	29.01 s	36.25	---	---	---	---	68.25
6.70	34,124	299.70	32.39 ic	2.86 ic	---	---	29.53 s	45.68	---	---	---	---	78.07
6.80	35,003	299.80	32.78 ic	2.74 ic	---	---	30.04 s	55.81	---	---	---	---	88.58
6.90	35,883	299.90	33.15 ic	2.63 ic	---	---	30.52 s	66.61	---	---	---	---	99.75
7.00	36,763	300.00	33.52 ic	2.52 ic	---	---	30.99 s	78.00	---	---	---	---	111.51

...End

Pond Report

Pond No. 1 - Stormwater Basin #1

Pond Data

Contours -User-defined contour areas. Conic method used for volume calculation. Begining Elevation = 293.00 ft

Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	293.00	1,951	0	0
1.00	294.00	2,711	2,320	2,320
2.00	295.00	3,567	3,129	5,449
3.00	296.00	4,529	4,038	9,487
4.00	297.00	5,567	5,039	14,526
5.00	298.00	6,713	6,130	20,656
6.00	299.00	7,923	7,309	27,965
7.00	300.00	9,704	8,798	36,763


Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 24.00	18.00	Inactive	0.00
Span (in)	= 24.00	18.00	0.00	0.00
No. Barrels	= 1	1	1	0
Invert El. (ft)	= 294.00	294.50	0.00	0.00
Length (ft)	= 75.00	0.67	0.00	0.00
Slope (%)	= 0.67	0.00	0.00	n/a
N-Value	= .012	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	Yes	No	No

Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 7.33	30.00	Inactive	0.00
Crest El. (ft)	= 297.50	299.00	0.00	0.00
Weir Coeff.	= 3.33	2.60	3.33	3.33
Weir Type	= 1	Broad	---	---
Multi-Stage	= Yes	No	No	No
Exfil.(in/hr)	= 0.000 (by Wet area)			
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).



Project Excavation/Fill Permit

By CJP

Date 07/26/21

Location 10/36 Main Street, Monroe CT

Checked LAM

Date 07/26/21

Bold one: **Existing** Proposed

Existing Drainage Area 1 (EDA-1)

1. Runoff Curve Number (CN)

Soil Name and hydrologic group (Appendix A)	Cover description (cover type, treatment, and hydrologic condition; percent impervious; unconnected/connected impervious area ratio)	CN ¹			Area <input checked="" type="checkbox"/> acres <input type="checkbox"/> mi ² <input type="checkbox"/> %	Product of CN x area
		Table 2-2	Fig. 2-3	Fig. 2-4		
B	Impervious Area	98			3.93	385.14
B	Pervious Area - Fair	69			3.89	268.41
A	Woods - Fair	39			0.72	28.08
B	Woods - Fair	60			5.54	332.40
B	Gravel Area	85			0.60	51.00
A	Pervious Area - Fair	49			0.17	8.33
						0.00
						0.00
Totals =					14.85	1073.36

¹ Use only one CN source per line

CN (weighted) = $\frac{\text{total product}}{\text{total area}} = \frac{1073.36}{14.85} = 72.28$ Use CN = **72**

Project Excavation/Fill Permit

By CJP

Date 07/26/21

Location 10/36 Main Street, Monroe CT

Checked LAM

Date 07/26/21

Bold one: Existing **Proposed**

Proposed Drainage Area 1A (PDA-1A)

1. Runoff Curve Number (CN)

Soil Name and hydrologic group (Appendix A)	Cover description (cover type, treatment, and hydrologic condition; percent impervious; unconnected/connected impervious area ratio)	CN ¹			Area <input checked="" type="checkbox"/> acres <input type="checkbox"/> mi ² <input type="checkbox"/> %	Product of CN x area
		Table 2-2	Fig. 2-3	Fig. 2-4		
B	Impervious Area	98			0.29	28.42
B	Pervious Area - Good	61			11.21	683.81
A	Pervious Area - Good	39			0.53	20.67
						0.00
						0.00
						0.00
						0.00
						0.00
Totals =					12.03	732.90

¹ Use only one CN source per line

CN (weighted) = $\frac{\text{total product}}{\text{total area}} = \frac{732.90}{12.03} = 60.92$ Use CN = **61**

Project Excavation/Fill Permit

By CJP

Date 07/26/21

Location 10/36 Main Street, Monroe CT

Checked LAM

Date 07/26/21

Bold one: Existing **Proposed**

Proposed Drainage Area 1B (PDA-1B)

1. Runoff Curve Number (CN)

Soil Name and hydrologic group (Appendix A)	Cover description (cover type, treatment, and hydrologic condition; percent impervious; unconnected/connected impervious area ratio)	CN ¹			Area <input checked="" type="checkbox"/> acres <input type="checkbox"/> mi ² <input type="checkbox"/> %	Product of CN x area
		Table 2-2	Fig. 2-3	Fig. 2-4		
B	Impervious Area	98			0.04	3.92
B	Pervious Area - Good	61			1.50	91.50
A	Pervious Area - Good	39			0.27	10.53
						0.00
						0.00
						0.00
						0.00
						0.00
Totals =					1.81	105.95

¹ Use only one CN source per line

CN (weighted) = $\frac{\text{total product}}{\text{total area}} = \frac{105.95}{1.81} = 58.54$ Use CN = **59**

Project Excavation/Fill Permit

By CJP

Date 07/26/21

Location 10/36 Main Street, Monroe CT

Checked LAM

Date 07/26/21

Bold one: Existing **Proposed**

Proposed Drainage Area 1C (PDA-1C)

1. Runoff Curve Number (CN)

Soil Name and hydrologic group (Appendix A)	Cover description (cover type, treatment, and hydrologic condition; percent impervious; unconnected/connected impervious area ratio)	CN ¹			Area <input checked="" type="checkbox"/> acres <input type="checkbox"/> mi ² <input type="checkbox"/> %	Product of CN x area
		Table 2-2	Fig. 2-3	Fig. 2-4		
B	Impervious Area	98			0.01	0.98
B	Pervious Area - Good	61			0.32	19.52
A	Pervious Area - Good	39			0.68	26.52
						0.00
						0.00
						0.00
						0.00
						0.00
Totals =					1.01	47.02

¹ Use only one CN source per line

CN (weighted) = $\frac{\text{total product}}{\text{total area}} = \frac{47.02}{1.01} = 46.55$ Use CN = **47**

Project Excavation/Fill Permit By CJP Date 07/26/21
 Location 10/36 Main Street, Monroe, CT Checked LAM Date 07/26/21
 Bold One: **Present** Developed
 Bold One: **T_c** T_t through subarea Existing Drainage Area 1 (EDA-1)

NOTES: Space for as many as two segments per flow type can be used for each worksheet.

Include a map, schematic, or description of flow segments.

Sheet flow (Applicable to T_c Only)

1. Surface description (table 3-1)
2. Manning's roughness coeff., n (table 3-1)
3. Flow Length, L (total L ≤ 300 ft)
4. Two-yr 24-hr rainfall, P₂
5. Land slope, s

$$T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5} S^{0.4}}$$

Compute T_t

Segment ID	AB	
	Dense Grasses	
	0.240	
ft	150	
in	3.56	
ft/ft	0.040	
hr	0.236	+
		=
		0.236

Shallow concentrated flow

7. Surface description (paved or unpaved)
8. Flow length, L
9. Watercourse slope, s
10. Average velocity, V (Conn DOT Equations 6.C.4 & C.C.5)

$$T_t = \frac{L}{3600 V}$$

Compute T_t

Segment ID	BC	CD	DE	EF
	unpaved	unpaved	paved	unpaved
ft	130	220	330	66
ft/ft	0.11	0.03	0.04	0.09
ft/s	5.28	2.88	4.04	4.84
hr	0.007	+	0.021	+
			0.023	+
				0.004

Channel flow

12. Cross sectional flow area, a
13. Wetted perimeter, p_w
14. Hydraulic radius, r
15. Channel slope, s
16. Manning's roughness coeff., n

$$r = \frac{a}{p_w}$$

Compute r

$$V = \frac{1.49 r^{2/3} s^{1/2}}{n}$$

Compute V

$$T_t = \frac{L}{3600 V}$$

Compute T_t

Segment ID		
ft ²		
ft		
ft		
ft/ft		
ft/s		
hr		+
		=
		0.000
		Hours = 0.291
		Minute = 17.5

20. Watershed or subarea T_c or T_t (add T_t in steps 6, 11, 19)

Project Excavation/Fill Permit By CJP Date 07/26/21
 Location 10/36 Main Street, Monroe, CT Checked LAM Date 07/26/21
 Bold One: Present **Developed**
 Bold One: **T_c** **T_t** through subarea Proposed Drainage Area 1A (PDA-1A)

NOTES: Space for as many as two segments per flow type can be used for each worksheet.

Include a map, schematic, or description of flow segments.

Sheet flow (Applicable to T_c Only)

1. Surface description (table 3-1)
2. Manning's roughness coeff., n (table 3-1)
3. Flow Length, L (total L ≤ 300 ft)
4. Two-yr 24-hr rainfall, P₂
5. Land slope, s

$$T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5} s^{0.4}}$$

Compute T_t

Segment ID	AB	BC
	Dense Grasses	Dense Grasses
	0.240	0.240
	69.72	80.28
	3.56	3.56
	0.14	0.01
	0.078	0.288

= 0.366

Shallow concentrated flow

7. Surface description (paved or unpaved)
8. Flow length, L
9. Watercourse slope, s
10. Average velocity, V (Conn DOT Equations 6.C.4 & C.C.5)

$$T_t = \frac{L}{3600 V}$$

Compute T_t

Segment ID	CD	DE	EF
	unpaved	unpaved	unpaved
	171	18	247
	0.01	0.33	0.02
	1.35	9.31	2.04
	0.035	0.001	0.034

= 0.069

Channel flow

12. Cross sectional flow area, a
13. Wetted perimeter, p_w
14. Hydraulic radius, r
15. Channel slope, s
16. Manning's roughness coeff., n

$$r = \frac{a}{p_w}$$

Compute r

$$V = \frac{1.49 r^{2/3} s^{1/2}}{n}$$

Compute V

$$T_t = \frac{L}{3600 V}$$

Compute T_t

Segment ID	FG	GH
	12	14
	11	16
	1.09091	0.87500
	0.02	0.36
	0.025	0.033
	8.93	24.78
	212	88
	0.007	0.001

= 0.008

20. Watershed or subarea T_c or T_t (add T_t in steps 6, 11, 19)

Hours = 0.443

Minutes = 26.6

Project Excavation/Fill Permit By CJP Date 07/26/21
 Location 10/36 Main Street, Monroe, CT Checked LAM Date 07/26/21
 Bold One: Present **Developed**
 Bold One: **T_c** **T_t** through subarea Proposed Drainage Area 1B (PDA-1B)

NOTES: Space for as many as two segments per flow type can be used for each worksheet.

Include a map, schematic, or description of flow segments.

Sheet flow (Applicable to T_c Only)

1. Surface description (table 3-1)
2. Manning's roughness coeff., n (table 3-1)
3. Flow Length, L (total L ≤ 300 ft)
4. Two-yr 24-hr rainfall, P₂
5. Land slope, s

$$T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5} s^{0.4}}$$

Compute T_t

Segment ID	AB	BC
	Pavement	Dense Grasses
	0.011	0.240
	32.7	81.9
	3.56	3.56
	0.05	0.09
	0.006	0.104
	+ = 0.110	

Shallow concentrated flow

7. Surface description (paved or unpaved)
8. Flow length, L
9. Watercourse slope, s
10. Average velocity, V (Conn DOT Equations 6.C.4 & C.C.5)

$$T_t = \frac{L}{3600 V}$$

Compute T_t

Segment ID	CD	DE
	unpaved	unpaved
	373.1	58.5
	0.01	0.41
	1.69	10.33
	0.061	0.002
	+ = 0.063	

Channel flow

12. Cross sectional flow area, a
13. Wetted perimeter, p_w
14. Hydraulic radius, r
15. Channel slope, s
16. Manning's roughness coeff., n

$$r = \frac{a}{p_w}$$

Compute r

$$V = \frac{1.49 r^{2/3} s^{1/2}}{n}$$

Compute V

$$T_t = \frac{L}{3600 V}$$

Compute T_t

Segment ID	EF	EF
	10	10
	12	12
	0.83333	0.83333
	0.064	0.16
	0.033	0.025
	10.12	21.11
	78.5	37.3
	0.002	0.000
	+ = 0.003	

20. Watershed or subarea T_c or T_t (add T_t in steps 6, 11, 19)

Hours	=	0.175
Minutes	=	10.5

Project Excavation/Fill Permit By CJP Date 07/26/21
 Location 10/36 Main Street, Monroe, CT Checked LAM Date 07/26/21

Bold One: Present **Developed**

Bold One: **T_c** **T_t** through subarea Proposed Drainage Area 1C (PDA-1C)

NOTES: Space for as many as two segments per flow type can be used for each worksheet.

Include a map, schematic, or description of flow segments.

Sheet flow (Applicable to T_c Only)

1. Surface description (table 3-1)
2. Manning's roughness coeff., n (table 3-1)
3. Flow Length, L (total L ≤ 300 ft)
4. Two-yr 24-hr rainfall, P₂
5. Land slope, s

$$T_t = \frac{0.007(nL)^{0.8}}{P_2^{0.5} s^{0.4}}$$

Compute T_t

Segment ID	AB		
	Dense Grasses		
	0.240		
	130		
ft			
	3.56		
in			
	0.06		
ft/ft			
	0.180	+	
hr			= 0.180

Shallow concentrated flow

7. Surface description (paved or unpaved)
8. Flow length, L
9. Watercourse slope, s
10. Average velocity, V (Conn DOT Equations 6.C.4 & C.C.5)

$$T_t = \frac{L}{3600 V}$$

Compute T_t

Segment ID			
ft			
ft/ft			
ft/s			
hr		+	
			=

Channel flow

12. Cross sectional flow area, a
13. Wetted perimeter, p_w
14. Hydraulic radius, r
15. Channel slope, s
16. Manning's roughness coeff., n

$$r = \frac{a}{p_w}$$

Compute r

$$V = \frac{1.49 r^{2/3} s^{1/2}}{n}$$

Compute V

$$T_t = \frac{L}{3600 V}$$

Compute T_t

Segment ID			
ft ²			
ft			
ft			
ft/ft			
ft/s			
ft			
hr		+	
			= 0.000

20. Watershed or subarea T_c or T_t (add T_t in steps 6, 11, 19) **Hours = 0.180**

Minutes = 10.8

WATER QUALITY VOLUME (WQV) COMPUTATIONS FOR DRAINAGE BASIN PDA-1A

Project: Excavation/Filling Permit Application
Location: 10 & 36 Main Street, Monroe, Connecticut
Date: 07/26/21

Water Quality Volume Calculations:

$$WQV = \frac{(1)(R)(A)}{12}$$

Where:
 WQV = water quality volume (ac-ft)
 R = volumetric runoff coefficient = 0.05+0.009(I)
 I = percent impervious cover (see below)
 A = site area in acres

$$I = \frac{A_{IMP}}{A_{TOT}} \times 100$$

Where:
 I = percent impervious cover
 A_{IMP} = area of impervious cover
 A_{TOT} = total area of watershed

Watershed Description:

PDA-1A

Area of impervious coverage, A _{IMP}	<input type="text" value="0.31"/>	Acres	
Total area of watershed, A _{TOT}	<input type="text" value="14.85"/>	Acres	
Percent impervious cover, I	<input type="text" value="2.09"/>	%	
Volumetric runoff coefficient, R	<input type="text" value="0.07"/>		
Water Quality Volume, WQV	<input type="text" value="0.085"/>	ac-ft	<input type="text" value="3,708"/> cf

APPENDIX C
INSPECTIONS

Excavation/Fill Permit Progress Report Form



Title: 10 & 36 Main Street Excavation/Fill Permit
Location: 10 & 36 Main Street, Monroe, CT
Permit: EFP XXXX-XX

IL #: XX
Project #: 2008001
Field Date: XX/XX/XXXX

EXCAVATION/FILL PERMIT PROGRESS REPORT

Name(s) of Individual(s) performing inspection:		AM	PM
Name of Inspecting Engineer/Position	Weather:	XXXXX	XXXXXX
	Temperature:	H: XX°F	L: XX°F

Time of Inspection:

Start: XX A.M.	Fill amount imported since last inspection:	±XXXX CY
End: XX A.M.	Fill amount imported to date:	±XXXX CY

Work Completed

Unanticipated Field Work/Delays

Material Report

Source of Material:		
Monthly Import Amount:		Cumulative Import Amount:
Is Import Material Contaminated?		Method of Determination:

Condition of Site Access and Control Measures

Condition of Soil Erosion and Sedimentation Control Measures

Condition of Drainage Control Measures & Corrective or Added Measures

Additional Inspection Required:	YES	NO	If Yes, Date: N/A
--	-----	----	--------------------------

Inspector(s) Signature(s): _____

APPENDIX D
PLANS

Grading & Soil Erosion Control Plan (Sheet 2.21)
Reclamation Plan (Sheet 2.61)

EROSION CONTROL AND SEDIMENT CONTROL NOTES

- PRIOR TO THE START OF CONSTRUCTION, A PRECONSTRUCTION MEETING WITH THE ENGINEER AND THE TOWN OF MONROE AND USE STAFF IS REQUIRED.
- ACTUAL LOCATIONS AND APPLICATIONS OF EROSION CONTROL DEVICES SHALL BE DETERMINED IN THE FIELD PRIOR TO THE START OF CONSTRUCTION BASED ON THE EROSION AND SEDIMENT CONTROL STRATEGY. THE STRATEGY WILL REQUIRE THE CONTRACTOR TO PROVIDE APPROPRIATE CONTROLS SUCH AS STRUCTURAL PRACTICES, MAINTENANCE, AND STABILIZATION PRACTICES ALONG WITH THE PROPER DISCHARGE OR Dewatering WASTEWATERS.
- LIMITS OF DISTURBANCE SHALL BE FLAGGED IN THE FIELD BY A LICENSED SURVEYOR AND VERIFIED PRIOR TO INITIATION OF CONSTRUCTION.
- EROSION AND SEDIMENT CONTROL DEVICES SHALL BE INSTALLED PRIOR TO ANY FILLING. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE STANDARD AND SPECIFICATIONS OF THE STATE OF CT DEEP 2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL HANDBOOK, AND 2001 CONNECTICUT STORMWATER QUALITY MANUAL. CONTROL DEVICES CONTINGENT ON INSPECTION APPROVAL BY THE TOWN OF MONROE LAND USE STAFF.
- ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED, FUNCTIONING, AND INSPECTED BY THE TOWN OF MONROE AND USE STAFF PRIOR TO ANY SITE DISTURBANCE. ADDITIONAL MEASURES MAY BE REQUIRED DURING THE COURSE OF CONSTRUCTION AND SHALL BE IMPLEMENTED AS NEEDED. ALL SEDIMENT AND EROSION CONTROL MEASURES ARE TO BE INSPECTED PRIOR TO A HEAVY RAIN, IMMEDIATELY AFTER AND AT LEAST DAILY DURING PROLONGED RAIN EVENTS. ANY AND ALL DEFICIENCIES MUST BE CORRECTED WITHIN 24 HOURS OF DISCOVERY.
- ALL GRADED AREAS WITH SLOPES STEEPER THAN 3 HORIZONTAL TO 1 VERTICAL SHALL BE STABILIZED WITH JUTE NETTING.
 - LAND GRADING.
 - AREAS TO BE FILLED SHALL BE CLEARED, GRUBBED AND STRIPPED OF UNSUITABLE MATERIAL.
 - ALL FILL SHALL BE COMPACTED AS REQUIRED TO REDUCE EROSION SLIPPAGE, SETTLEMENT, SUBSIDENCE, OR OTHER RELATED PROBLEMS.
 - MATERIAL SHALL BE FREE OF BRUSH, RUBBISH, ROCKS LOGS, STUMPS, BUILDING DEBRIS AND OTHER UNSUITABLE MATERIALS THAT WOULD INTERFERE WITH OR PREVENT CONSTRUCTION OF SATISFACTORY FILLS.
- WHEN ALL GRADED AREAS ARE PERMANENTLY STABILIZED, REMOVE ALL EROSION AND SEDIMENT CONTROL DEVICES. AFTER ALL REMOVAL, INSPECTION TO BE PERFORMED BY TOWN OF MONROE LAND USE STAFF.
- IT SHALL BE THE RESPONSIBILITY OF THE SITE DEVELOPMENT CONTRACTOR TO ENSURE PROPER IMPLEMENTATION OF THE SOIL EROSION AND SEDIMENT CONTROLS AS SHOWN ON THIS PLAN, AND SHALL INCLUDE BUT NOT BE LIMITED TO INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL

- PARTIES OF SUCH REQUIREMENTS AND NOTIFICATIONS OF ANY TRANSFER OF THIS RESPONSIBILITY TO OTHER PARTIES. CONTRACTOR: STUART RUDKIN, CONTACT NUMBER: (203) 505-1376.
- ANY DISTRIBUTION AREA AND PILES PLANNED TO BE LEFT MORE THAN 14 DAYS WILL HAVE TO BE SEED OR MULCH IMMEDIATELY.
- WHEN ALL SURFACES ARE PERMANENTLY STABILIZED, ANY REMAINING SEDIMENT AND EROSION CONTROL DEVICES SHALL BE REMOVED AND ALL TRAPPED SEDIMENT SHALL BE REMOVED. ALL CATCH BASIN SLUMPS SHALL BE CLEANED.
- CONSTRUCTION ACTIVITIES AT THE PROJECT SITE WILL RESULT IN EMISSIONS OF FUGITIVE DUST TO THE ATMOSPHERE. THE QUANTITY OF FUGITIVE DUST GENERATED WILL BE CONTROLLED BUT IS DEPENDENT UPON WEATHER CONDITIONS. FUGITIVE DUST PARTICLES HAVE A GREATER PROPENSITY TO REMOVAL DURING DRY AND BREEZY METEOROLOGICAL CONDITIONS. CONSTRUCTION ACTIVITIES AT THE SITE WHICH WILL RESULT IN PILES AND CONSTRUCTION TRAFFIC. THE CONTRACTOR WILL IMPLEMENT THE FOLLOWING REASONABLE PRECAUTIONS DURING CONSTRUCTION TO MINIMIZE THE GENERATION OF FUGITIVE DUST:
 - USE WATER FOR DUST CONTROL OF ACTIVE CONSTRUCTION AREAS, ACTIVE UNPAVED ROADS, AND OTHER SURFACES WHICH CAN FIVE RISE TO AIRBORNE DUST. A TYPICAL PRACTICE TO BE FOLLOWED DURING SITE GRADING WILL BE TO FOLLOW THE EARTH MOVING EQUIPMENT WITH A WATER TRUCK TO IMMEDIATELY WET THE NEW DISTURBED AREA.
 - APPLY SEED FOR A VEGETATIVE COVER ON STORAGE PILES, ESPECIALLY THOSE THAT WILL REMAIN DORMANT FOR AN EXTENDED PERIOD.
 - THE CONTRACTOR MUST CLEAN SWEEP DAILY ALL ON-SITE PAVED ROADS AND THAT PORTION OF ANY SURROUNDING ROADS WHICH ARE USED BY CONSTRUCTION TRAFFIC FOR THE DURATION OF THE PROJECT.
 - INSTITUTE A MAXIMUM ON SITE SPEED LIMIT OF 10 MPH PER HOUR.
 - THE CONTRACTOR IS RESPONSIBLE FOR DUST CONTROL DURING THE CONSTRUCTION PROCESS. THE CONSTRUCTION MANAGER SHALL INSPECT THE SITE TO ASSURE DUST IS ADEQUATELY CONTROLLED. IF THE CONSTRUCTION MANAGER OR OWNERS REPRESENTATIVE FEELS DUST CONTROL MEASURES ARE NOT ADEQUATE THE CONTRACT SHALL BE REQUIRED TO INCREASE THESE MEASURES AS DIRECTED BY THE CONSTRUCTION MANAGER.
- ALL CONSTRUCTION ACTIVITIES SHALL COMPLY WITH THE TOWN OF MONROE ZONING REGULATIONS.
- A STORMWATER MANAGEMENT SYSTEM MAINTENANCE SCHEDULE SHALL BE IMPLEMENTED AND OFFICIALLY RECORDED BY THE INDIVIDUAL IDENTIFIED IN NOTE 8 ABOVE. THE SCHEDULE SHALL INCLUDE AS A MINIMUM:
 - INSPECTED WEEKLY, AND AFTER ANY STORM EVENT GENERATING MORE THAN 0.5 INCHES OF RAIN.

- A WEEKLY INSPECTION OF THE SITE SHALL BE CONDUCTED FOR SURFACE DEBRIS.
- A MONTHLY INSPECTION OF ALL STORMWATER STRUCTURES AND OUTFALLS SHALL BE CONDUCTED FOR FLOATING OR SURFACE DEBRIS SEDIMENT.
- STRUCTURES AND OUTFALLS SHALL BE CLEANED OF SEDIMENT AND DEBRIS AT LEAST ONCE A YEAR DURING THE MONTH OF APRIL AND AT OTHER TIMES AS NECESSARY TO PREVENT THE DISCHARGE OF POLLUTANTS FROM STRUCTURES OR OUTFALLS.
- ALL DRIVES SHALL BE SWEEP CLEAN OF SAND, LITTER AND OTHER POSSIBLE POLLUTANTS AT LEAST TWICE A YEAR, ONCE BETWEEN NOVEMBER 14 AND DECEMBER 15 AND ONCE DURING THE MONTH OF APRIL AND AT OTHER TIMES AS DIRECTED BY THE TOWN OF MONROE.
- A STOCKPILE OF SEDIMENT AND EROSION CONTROLS SHALL BE KEPT ON SITE AT ALL TIMES. THIS WILL CONSIST OF AT LEAST 24 HAY BALES, UNDER COVER, EXTRA STONE FOR THE ANTI-TRACKING APRON, AT LEAST 100 FEET OF SILT FENCE AND 100 SQUARE YARDS OF NON-WOVEN FILTER FABRIC. ADDITIONAL MEASURES MAY BE REQUIRED BY THE SITE MONITOR OR THE TOWN OF MONROE. THESE MEASURES ARE TO BE INSTALLED BY THE REQUEST DATE.
- REPLACE CONSTRUCTION ENTRANCE WHEN THE CAPACITY OF THE APRON HAS REACHED THE 5% VOLUME.
- SEDIMENT REMOVED FROM CONSTRUCTION STRUCTURES WILL BE DISPOSED OF IN A MANNER WHICH IS CONSISTENT WITH THE INTENT OF THESE PLANS.
- WHERE CONSTRUCTION ACTIVITIES HAVE PERMANENTLY CEASED OR HAVE TEMPORARILY BEEN SUSPENDED FOR MORE THAN SEVEN DAYS, OR WHEN FINAL GRADES ARE REACHED IN ANY PORTION OF THE SITE, STABILIZATION PRACTICES SHALL BE IMPLEMENTED WITHIN THREE DAYS.
- TEMPORARY FACILITIES (SWALES, CULVERTS, CHECK DAMS, ETC.) MAY BE UTILIZED AS NECESSARY TO HELP FACILITATE PROPER FUNCTIONING AND MAINTENANCE OF THE SITE.

EQUIPMENT INFORMATION

- 2 LARGE EXCAVATORS 380-480 SIZE
- 1 SMALL EXCAVATOR 85-160 SIZE
- 1 TRACK DOZER 450-750 SIZE
- 2 WHEEL LOADERS WA 500 SIZE
- 2 24 TON TRAILER DUMP TRUCKS
- 2 VIBRATORY COMPACTOR ROLLERS
- 1 105,000 LB JAW CRUSHER
- 1 80' STACKING CONVEYOR

APPROXIMATELY 167,945 CUBIC YARD OF MATERIAL WILL BE IMPORTED, USING A CONVERSION RATE OF 1.37 TON/CY AND A MAXIMUM LOADING RATE OF 24 TON/TRUCK, APPROXIMATELY 9,587 TRUCK LOADS OF FILL WILL BE IMPORTED TO THE PROPERTY.


PLANNING & ZONING WAIVERS REQUIRED

- §6-49 C - NO CHANGE IN CONTOUR SHALL BE MADE WITHIN TWENTY-FIVE (25) FEET OF ANY PROPERTY LINE.
 - §6-49 D - NO ARTIFICIAL SLOPE GREATER THAN FOURTEEN DEGREES (14°) TO THE HORIZONTAL (OR MAXIMUM FOUR FEET HORIZONTAL TO ONE FOOT VERTICAL) SHALL BE CREATED WITHIN FIFTY FEET OF ANY PROPERTY LINE.
 - §6-49 P - NO SORTING, GRADING, CRUSHING OR OTHER MACHINERY FOR TREATMENT OR PROCESSING OF MATERIAL BEING REMOVED OR DEPOSITED SHALL BE ERRECTED, MAINTAINED OR OPERATED ON THE PREMISES FOR WHICH A PERMIT MAY BE GRANTED, EXCEPT IN AN INDUSTRIAL DISTRICT OR IN ALL OTHER DISTRICTS WHERE CONTROLLED ROCK CRUSHING, SCREENING AND PROCESSING MAY BE PERMITTED BY THE COMMISSION ON A LIMITED SHORT DURATION BASIS AS PART OF SITE DEVELOPMENT AND CONSTRUCTION PREPARATION, PROVIDED:
 - (1) SUCH CONTROLLED ACTIVITIES WILL REDUCE CONSTRUCTION TRAFFIC BY USE OF MATERIALS ON-SITE.
 - (2) SUCH CONTROLLED ACTIVITIES WILL NOT INVOLVE MINING OR EXCAVATION OF MORE THAN NECESSARY TO ACHIEVE SITE PREPARATION OF AN APPROVED PROJECT.
- ALL PERMITTED SUCH ACTIVITIES REGARDLESS OF PERMITTED LOCATION SHALL NOT INCLUDE, PERMIT OR INVOLVE MATERIALS FROM OFFSITE LOCATIONS.

CONSTRUCTION SCHEDULE

THE ANTICIPATED STARTING DATE FOR CONSTRUCTION IS SUMMER 2021 WITH COMPLETION ANTICIPATED BY SUMMER 2023. APPROPRIATE EROSION CONTROL MEASURES AS DESCRIBED HEREIN, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ALL SITE CLEARING OR CONSTRUCTION ACTIVITY. SCHEDULE WORK TO MINIMIZE THE LENGTH OF TIME THAT BARE SOIL IS EXPOSED.

LEGEND



GENERAL NOTES

- EXISTING SITE CONDITIONS TAKEN FROM A PLAN ENTITLED "IMPROVEMENT LOCATION SURVEY PREPARED FOR VISHAY SPRAY & PAINT, INC. BY JOHN J. MONROE, CONNECTICUT", DATED: MAY 21, 2021, SCALE: 1" = 40'. PREPARED BY ACCURATE LAND SURVEYING, LLC.
- THE CONTRACTOR SHALL PRESERVE EXISTING VEGETATION WHERE POSSIBLE AND/OR AS NOTED ON DRAWINGS.
- OPERATIONS SHALL BE UNDERTAKEN ON THE SITE EXCEPT BETWEEN THE HOURS OF 8:00 AM AND 5:00 PM MONDAY THROUGH FRIDAY, EXCEPT WITH APPROVAL OF THE COMMISSION. THERE SHALL BE NO BLASTING ON THE SITE. NO ACTIVITY OF ANY TYPE SHALL BE CONDUCTED ON ANY LEGAL HOLIDAY DECLARED BY THE GOVERNMENT OF THE STATE OF CONNECTICUT OR THE UNITED STATES. TRUCK TRAFFIC IS LIMITED TO BETWEEN 9:00 AM AND 4:00 PM DAILY.
- THE PERMITTEE SHALL PROVIDE ENGINEERING PROGRESS REPORTS PREPARED BY A LICENSED CIVIL ENGINEER OR CIVIL ENGINEER ON A QUARTERLY BASIS. ADDITIONALLY, THE COMMISSION MAY AT ANY TIME DURING THE PERMIT DURATION REQUIRE AN ENGINEERING PROGRESS REPORT FROM THE PERMITTEE, TO BE MADE BY A LICENSED CIVIL ENGINEER. IF SUCH REPORT IS NOT RECEIVED BY THE COMMISSION WITHIN THIRTY (30) DAYS FROM THE DATE OF SUCH REQUEST, THE COMMISSION MAY ENGAGE A PROFESSIONAL ENGINEER OR LAND SURVEYOR TO DETERMINE COMPLIANCE WITH THE TERMS OF THIS REGULATION AND ALL EXPENSES IN CONNECTION THEREWITH SHALL BE PAID BY THE PERMITTEE.
- THE TOP LAYER OF TOPSOIL FOR A DEPTH OF SIX INCHES SHALL BE SET ASIDE ON THE PREMISES AND SHALL BE RE-SPREAD IN ACCORDANCE WITH THE APPROVED CONTOUR LINES WITHIN THIRTY (30) DAYS FOLLOWING THE EXPIRATION OR REVOCATION OF THE PERMIT OR COMPLETION OF THE WORK, WHICHEVER OCCURS EARLIER.
- THE PERMITTEE SHALL PROVIDE ENGINEERING PROGRESS REPORTS PREPARED BY A LICENSED CIVIL ENGINEER (EQUIPMENT MUFFLERS, ETC.) SHALL BE TAKEN TO MINIMIZE THE NOISANCE OF NOISE AND FLYING DUST OR ROCK AND LIGHTING.
- UPON COMPLETION OF THE SITE FILLING/EXCAVATION ACTIVITIES, THE FINAL CONDITION OF THE REMAINING SITE ACCESS TO BE IN THE FORM OF THE ANTI-TRACKING PAD AND THE FRONTAGE CONDITIONS ARE TO BE AS SPECIFIED ON THE RECLAMATION PLAN (SHEET 2.61) ALL FILL MATERIAL BROUGHT TO THE SITE SHALL CONFORM TO THE CT DEEP STANDARDS FOR "CLEAN FILL". ANY FILL FROM ANY OTHER SITE OTHER THAN THE ONE SPECIFIED ON THIS PLAN WILL BE INSPECTED PRIOR TO FILLING THE SITE AND WILL BE SUBJECT TO RANDOM TESTING.
- THERE SHALL BE NO SIGNS PERMITTED (EXCEPT CUSTOMARY TRAFFIC CONTROL, SAFETY, AND NO TRASPASSING SIGNS AS MAY BE AUTHORIZED BY THE PLANNING AND ZONING ADMINISTRATOR).

CONSTRUCTION SEQUENCE

- INSTALL STABILIZED CONSTRUCTION ENTRANCE/EXIT.
- INSTALL SILT FENCING ON THE SITE. CLEAR ONLY THOSE AREAS NECESSARY TO INSTALL SILT FENCE.
- PREPARE TEMPORARY PARKING AND STORAGE AREAS.
- HALT ALL ACTIVITIES AND CONTACT THE ENGINEER OF RECORD TO PERFORM INSPECTION AND CERTIFICATION OF BEST MANAGEMENT PRACTICES (BMPs). GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT THE STORM WATER PRE-CONSTRUCTION MEETING WITH THE ENGINEER, AGENCIES AND DEMOLITION CONTRACTOR BEFORE PROCEEDING WITH CONSTRUCTION.
- CONSTRUCT AND STABILIZE SEDIMENT BASINS (WITH APPROPRIATE OUTFALL STRUCTURES (CLEAR ONLY THOSE AREAS NECESSARY TO INSTALL BASINS).
- BEGIN CLEARING AND GRUBBING THE SITE.
- INSTALL THE CONSTRUCTION TRAILER (WITH SUPPORT UTILITIES, ELECTRIC, WATER, ETC.)
- REMOVE THE EXISTING BITUMINOUS CONCRETE PAVEMENT AND BITUMINOUS CONCRETE CURB.
- INSTALL ADDITIONAL EROSION CONTROLS AS WORK PROGRESSES. TOPSOIL AND SEED SLOPES WHICH HAVE ACHIEVED FINAL SITE GRADING.
- IMMEDIATELY UPON DISCOVERING UNFORESEEN CIRCUMSTANCES POSING THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION, THE OPERATOR SHALL IMPLEMENT APPROPRIATE BEST MANAGEMENT PRACTICES TO ELIMINATE THE POTENTIAL FOR ACCELERATED EROSION AND/OR SEDIMENT POLLUTION.
- THROUGHOUT CONSTRUCTION, REMOVE SEDIMENT FROM BEHIND SILT FENCES, HAY BALES AND OTHER EROSION CONTROL DEVICES, AND FROM SEDIMENTATION BASINS AND SEDIMENT TRAPS AS REQUIRED. REMOVAL SHALL BE ON A PERIODIC BASIS (EVERY SIGNIFICANT RAINFALL OF 0.10 INCH OR GREATER). INSPECTION OF EROSION CONTROL MEASURES SHALL BE ON A WEEKLY BASIS AND AFTER EACH RAINFALL OF 0.50 INCHES OR GREATER. SEDIMENT COLLECTED SHALL BE DEPOSITED AND SPREAD EVENLY UPLAND ON SLOPES DURING CONSTRUCTION.
- THROUGHOUT THE CONSTRUCTION SEQUENCE, PERFORM INSPECTIONS SHALL BE INCORPORATED DURING THE PROCESSING OF THIS EXCAVATION AND FILL PERMIT AT SPECIFIC MILESTONES PER TOWN STAFF DIRECTION, AND AT LEAST MONTHLY INSPECTIONS.
- CONDUCT TIME GRADING.
- FERTILIZE SEED AND MULCH. SEED MIXTURE TO BE INSTALLED DURING THE SPRING OR FALL SEASON ONLY. USE EROSION CONTROL BLANKETS AS REQUIRED OR ORDERED FOR SLOPES GREATER THAN 3:1 AND AS SHOWN ON LANDSCAPE PLANS OR EROSION CONTROL PLANS. FOR TEMPORARY STABILIZATION BEYOND SEEDING DATES USE ANNUAL RYE AT 4.0 LBS./1,000 S.F., FERTILIZER WITH 10-10-10 AT 1.0 LBS. OF NITROGEN PER 1,000 S.F. AND LIME AT 100 LBS./1,000 S.F. (MAX.).
- UPON DIRECTION OF THE TOWN OF MONROE AGENT FOLLOWING THEIR FINAL INSPECTIONS HAVE BEEN PERFORMED AND CERTIFICATES OF COMPLETION FOR INLAND WETLAND AND EXCAVATION/FILLING HAVE BEEN ISSUED, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED THROUGH STABILIZATION OF THE SITE.

VOLUME SUMMARY

AREA	AREA OF DISTURBANCE	CUT (CY)	FILL (CY)	NET (CY)
REGULATED AREA	51,766 SF (1.19 AC)	2,680	2,029	651 (CUT)
BALANCE OF SITE	509,365 SF (11.69 AC)	12,539	180,980	167,139 (FILL)
TOTAL	561,131 SF (12.88 AC)	15,219	183,009	167,790 (FILL)

NOTE: NO FILL IS PLANNED WITHIN THE 100-YEAR FLOOD LIMIT.

SEDIMENT BASIN CALCULATIONS

SEDIMENT BASIN #1:
 CONTRIBUTING DRAINAGE AREA = 14.71± ACRES
 $V = [(DA)(ADR)(K)(2,000)(BS/TON)] / [(V)(43,560)(SQ. FT/AC)]$
 $V = [(14.71)(50)(40)(8)(2,000)] / [(100)(43,560)] = 0.1881 \text{ ACR-FY-YEAR}$
 $V = 4,709 \text{ CF-YEAR}$
 $V = (4,709 \text{ CF-YEAR})(2 \text{ YEARS}) = 9,418 \text{ CF}$
 REQUIRED WET STORAGE = 2 X 1 YEAR SEDIMENT STORAGE
 $V = (2)(4,709) = 9,418 \text{ CF}$
 REQUIRED BASIN #1 STORAGE = 9,418 CF
 SEDIMENT BASIN #1 STORAGE CAPACITY = 17,591 ± CF
 AT ELEV: 297.50'

GROUNDWATER MONITORING DATA

DATA COLLECTED BY SOLLI ENGINEERING, LLC, WEEKLY FROM 07/15/15 TO 06/14/16.
 MONITORING WELL 13 (MW-13)
 SURFACE ELEVATION = 291.70
 MINIMUM DEPTH TO GROUNDWATER = 0.88' - 290.82'


SELECT FILL REQUIREMENTS

- SELECT FILL MATERIAL AND SELECT BACKFILL MATERIAL, PLACED WITHIN AND ADJACENT TO PROPOSED LEACHING AREAS SHALL BE COMPRISED OF CLEAN SAND AND GRAVEL, FREE OF ORGANIC MATTER AND FOREIGN SUBSTANCES. THE FILL MATERIAL SHALL MEET THE FOLLOWING REQUIREMENTS UNLESS OTHERWISE APPROVED BY A PROFESSIONAL ENGINEER FOR USE WITHIN THE LEACHING AREA:
 - THE FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN (3) INCHES.
 - UP TO 4% OF THE DRY WEIGHT OF THE REPRESENTATIVE SAMPLE MAY BE RETAINED ON THE #4 SIEVE (THIS IS THE GRAVEL PORTION OF THE SAME).
 - THE MATERIAL THAT PASSES THE #4 SIEVE IS THEN REWEIGHED AND THE SIEVE ANALYSIS STARTED.
 - THE REMAINING SAMPLE SHALL MEET THE FOLLOWING GRADATION CRITERIA:

REQUIRED % PASSING	PERCENT PASSING WET SIEVE	PERCENT PASSING DRY SIEVE
#4	100	100
#10	70-100	70-100
#40	10-90	10-90
#100	0-20	0-5
#200	0-5	0-2.5

- PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75% IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10% AND THE #200 SIEVE DOES NOT EXCEED 5%.
- THE RESPONSIBILITY FOR THE PREPARATION OF A LEACHING AREA UTILIZING "SELECT MATERIAL" IS THAT OF THE LICENSED INSTALLER.
- THE INSTALLER SHALL TAKE THE NECESSARY STEPS TO PROTECT THE UNDERLYING NATURALLY OCCURRING SOILS FROM OVERCOMPACTATION AND CONSOLIDATION ONCE EXCAVATED.
- SELECT FILL SHALL BE PLACED BY A LICENSED INSTALLER.
- ANY TOPSOIL WITHIN SEPTIC AREA IS TO BE REMOVED AND REPLACED WITH SELECT FILL.
- FILL SHALL BE PLACED ON THE PERIMETER OF THE TRENCH AREA AND SPREAD WITH A SMALL CRAWLER, TRACTOR OR OTHER APPROVED MACHINERY.

Rev. #:	Date	Description




501 Main Street, Monroe, CT 06468 T: (203) 880-5455 F: (203) 880-9695
 351 Newbury Street, Boston, MA 02115 T: (617) 203-3160 F: (203) 880-9695

Drawn By: CJP
 Checked By: LAM
 Approved By: KMS
 Project #: 2008001
 Plan Date: 07/26/21
 Scale: 1" = 50'
 Kevin Solli, P.E.
 CT 25759


EXCAVATION/FILLING PERMIT APPLICATION

10 & 36 MAIN STREET
 MONROE, CONNECTICUT

Sheet Title: GRADING & SOIL EROSION CONTROL PLAN
 Sheet #: 2.21



Jul 27, 2021 - 10:21am
 Anthony #40
 X:\SE File\Project Data\2020\2008001 - 10 & 36 Main Street - Monroe, CT\Cadd Data\Excavation and Fill Permit\2008001-2.21.dwg



PRE VEGETATION MAP
SCALE: 1" = 100'



POST VEGETATION MAP
SCALE: 1" = 100'

LEGEND

	PROPERTY LINE
	ADJOINING LOT LINE
	MAJOR CONTOURS
	MINOR CONTOURS
	LIMIT OF DISTURBANCE
	EXISTING TREE LINE
	PROPOSED TREE LINE
	PREVIOUSLY DELINEATED WETLANDS
	WETLAND LINE
	LIMIT OF 100' UPLAND REVIEW AREA
	SEEDED LAWN AREA
	NEW ENGLAND CONSERVATION WILDLIFE MIX
	EXISTING WOODED AREA TO REMAIN
	CONSTRUCTION ENTRANCE

GENERAL NOTES


- EXISTING SITE CONDITIONS TAKEN FROM A PLAN ENTITLED "PROPERTY SURVEY OF 10 & 36 MAIN STREET, MONROE, CONNECTICUT" DATED: 05/21/21; SCALE: 1" = 60'; PREPARED BY ACCURATE LAND SURVEYING, LLC. REFER TO SAID PLAN FOR ALL DIMENSIONS, BEARINGS OR ANGLES OF PROPERTY LINES, EASEMENTS AND RIGHT-OF-WAYS.
- THE AREAS OF EXISTING VEGETATION HAVE BEEN FIELD VERIFIED BY A LICENSED LANDSCAPE ARCHITECT ON 05/27/21.
- SPECIES DEPICTED ON PRE-VEGETATION MAP INDICATE MAJOR PLANT ASSOCIATIONS AND ARE NOT INTENDED TO REPRESENT A DETAILED INVENTORY OF THE SITE'S PLANT MATERIAL.
- A SITE RESTORATION PLAN MUST BE IMPLEMENTED IN THE EVENT FUTURE DEVELOPMENT OF THE SITE DOES NOT MATERIALIZE WITHIN TWO (2) YEARS OF THE COMPLETION OF EXCAVATION.

LAWN SEED MIX

- PRIOR TO SEEDING, AREA IS TO BE TOPSOILED, FINE GRADED, AND RAKED OF ALL DEBRIS LARGER THAN 1" DIAMETER.
- THE FOLLOWING SEED MIX SHALL BE SOWN AT THE RATES AS DEPICTED:
 CREEPING RED FESCUE 1 LB. / 1,000 SF
 PERENNIAL RYEGRASS 3 LBS. / 1,000 SF
 KENTUCKY BLUEGRASS 1 LB. / 1,000 SF
- SEED MIX SHALL BE MULCHED WITH SALT HAY OR UNROTTED SMALL GRAIN STRAW AT A RATE OF 2 TONS / ACRE OR 90 LBS. / 1,000 SF.
- SEEDING DATES FOR THIS MIXTURE SHALL BE AS FOLLOWS:
 SPRING: APRIL 1 - MAY 31
 FALL: AUGUST 16 - OCTOBER 31
- GERMINATION RATES WILL VARY AS TO TIME OF YEAR FOR SOWING. CONTRACTOR TO IRRIGATE SEEDED AREA UNTIL AN ACCEPTABLE STAND OF COVER IS ESTABLISHED.
- ALL DISTURBED AREAS TO BE STABILIZED WITH SEED MIX AS SPECIFIED.

NEW ENGLAND CONSERVATION WILDLIFE MIX

- PRODUCED BY NEW ENGLAND WETLAND PLANTS, INC.; WWW.NEWP.COM; 820 WEST STREET, AMHERST, MA 01002; (413) 548-8000.
- PRIOR TO SEEDING, AREA IS TO BE TOPSOILED, FINE GRADED, AND RAKED OF ALL DEBRIS LARGER THAN 1" DIAMETER.
- THE SEED MIX SHALL BE APPLIED AT A RATE OF 1 LB. / 1,750 SQUARE FEET.
- SEED MIX SHALL BE MULCHED WITH SALT HAY OR UNROTTED SMALL GRAIN STRAW AT A RATE OF 2 TONS / ACRE OR 90 LBS. / 1,000 SF.
- SEEDING DATES FOR THIS MIXTURE SHALL BE AS FOLLOWS:
 SPRING: APRIL 1 - MAY 31
 FALL: AUGUST 16 - OCTOBER 31
- GERMINATION RATES WILL VARY AS TO TIME OF YEAR FOR SOWING. CONTRACTOR TO IRRIGATE SEEDED AREA UNTIL AN ACCEPTABLE STAND OF COVER IS ESTABLISHED.
- ALL DISTURBED AREAS TO BE STABILIZED WITH SEED MIX AS SPECIFIED.



SOLLI ENGINEERING
 501 Main Street, Monroe, CT 06468 T: (203) 880-5455 F: (203) 880-9695
 351 Newbury Street, Boston, MA 02115 T: (617) 203-3160 F: (203) 880-9695

Drawn By:	FLO
Checked By:	MFB
Approved By:	KMS
Project #:	2008001
Plan Date:	07/26/21
Scale:	1" = 100'
Mary Blackburn, P.L.A. CT 1499	

EXCAVATION/FILLING PERMIT APPLICATION
 10 & 36 MAIN STREET
 MONROE, CONNECTICUT

Sheet Title:	Sheet #:
RECLAMATION PLAN	2.61